



# Whole Building Blower Door Testing





## Collin Olson

- Senior Staff Physicist
- 25+ years experience in building science & performance
- Ph.D. from Univ. of Wisconsin, Madison

# PHIUS Commercial Building Standards


## PHIUS CORE COMM



<https://www.phius.org/phius-core-comm-standard-specifications>



- **Airtightness**  
Critical for building durability
- Phius sets a pass/fail certification requirement on airtightness. It is **per square foot of gross enclosure surface area** and has varying limits based on test pressure.
- Full building **pressurization and depressurization tests** are required to show compliance with this threshold.
- For most projects, the threshold is **0.060 CFM50 per square foot of enclosure**, but the exact requirements and protocol for each project can be found in the **Certification Guidebook**.




Airtightness is measured via a Blower Door Test

# Agenda

- Building Performance and Air Tightness
- Planning a Blower Door Test
- Running a Blower Door Test
- Interpreting Results & Building a Report

# What Happens During a Blower Door Test?

- A blower door test is typically done at an **induced** pressure difference of 50 (or 75) Pascals(Pa)\*
- The fan is turned on and adjusted to **change** the pressure difference between inside and outside the building by 50 (or 75) Pa and the flow is measured.




A Blower Door Test induces a pressure difference between inside and outside

\* - Note: To simplify the explanation, we will talk about a single point blower door test at 50 PA. The same principles hold for multi-point tests using different pressures.


# Considerations in Whole Building (Beyond Residential)

- Baseline To address variation from Wind and Stack effect
  - Measure at 4 locations, lowest variability
- Monitor stack at top and bottom
  - Ensure target pressures for the test move all the leaks in one direction for all test pressures
  - TECLOG will complete this calculation for you when running E3158 test standard

## Winter



## Summer




## What Season?



# Considerations in Whole Building (Beyond Residential)

- Single Zone Conditions
  - Partitions, floors and doors divide up spaces
  - Ensure that bottlenecked locations are within 10% of each other



# Agenda

- Building Performance and Air Tightness
- Planning a Blower Door Test
- Running a Blower Door Test
- Interpreting Results & Building a Report



# Planning a Blower Door Test

Process	Goals
Test Goals & Standards	Understand requirements of tests, metrics; Phius, <b>E779</b> , <b>E3158</b> , Envelope vs. Operational
Review blueprints	ID Test Boundaries, ID HVAC mechanicals
Determine # of Fans	Capacity to confirm compliance, etc.
HVAC Mechanical Prep	Sealing approach, equipment, etc.
AC Power	Ensure access to circuits needed
Plans with Building	Occupants, Safety, etc.




# Airtightness Units / Metrics

- **Airflow at a test pressure:**
  - CFM at 50 pascals (CFM50)
  - CFM at 75 pascals (CFM75)
- **Normalized Metrics**
  - **CFM50 per sq ft enclosure = CFM at 50 Pa per square foot of enclosure (5 or 6 sides of the box)**
  - **CFM75 per sq ft enclosure = CFM at 75 Pa per square foot of enclosure (5 or 6 sides of the box)**
  - ACH50 = Air Changes per Hour at 50 Pascals =  $CFM50 \cdot 60 / \text{Volume}$
  - SLA = ELA (4 Pa)/Conditioned Floor Area (both in same units)
- **Equivalent Leakage Areas**
  - ELA (4 pa) = the area of a theoretical hole (with rounded edges) in the building envelope that would leak as much as all of the building's actual holes at a pressure difference of 4 Pa. ELA (in square inches) approximately equals cfm50 divided by 18
  - EqLA (10 pa) = the area of a theoretical sharp-edged hole in the building envelope that would leak as much as all of the building's actual holes at a pressure difference of 10 Pa. EqLA (in square inches) approximately equals cfm50 divided by 10.


If all surfaces have same leakage per unit area  $\text{CFM}_{50}/\text{ft}^2 = 0.20$

10 ft




$$\text{CFM}_{50}/\text{ft}^2 = 0.20$$
$$\text{ACH}_{50} = 600 * 0.20 / 1000 * 60 = 7.2$$

20 ft



$$\text{CFM}_{50}/\text{ft}^2 = 0.20$$
$$\text{ACH}_{50} = 2400 * 0.20 / 8000 * 60 = 3.6$$

100 ft



$$\text{CFM}_{50}/\text{ft}^2 = 0.20$$
$$\text{ACH}_{50} = 60000 * 0.20 / 1000000 * 60 = 0.72$$

# How much air do I need?

- Maximum leakage rate specified
  - Bring enough to induce the specified pressure difference with the specified flowrate
  - E.g. Area enclosure (ft<sup>2</sup>) x 0.25 cfm/ft<sup>2</sup> at 75 pascals (ACE spec)
  - 0.6 ACH x enclosure volume (ft<sup>3</sup>) / 60 m/hr (passiv haus)
- Ordinary construction
  - 0.2 – 1.2 cfm/ft<sup>2</sup> at 75 pascals ?

**TEC has a Simple Excel Tool**

# Understanding Data Collection for ASTM E3158-18

Category	Subcategory	Requirement
<b>Pressure Uniformity</b>	Allowed pressure variation between spaces	≤ 10% of induced envelope pressure
	Min verification locations	Every 10 stories including top, bottom and middle floor
	Exceptions	If all rooms interconnected with 2 m <sup>2</sup> opening & total fan airflow at highest induced test pressure is < 6000 cfm, uniformity assumed
<b>Baseline Pressure</b>	Multi-point	Before & After (12 points min for 10 seconds each)
<b>Range of Test Pressures</b>	Multi-point	10 Pa ≤ Induced ΔP ≤ 100 Pa; min range = 25 Pa
<b># Test Points &amp; Duration</b>	Multi-point	≥ 10 points for at least 2x length of intervals used in baseline
<b>Reporting Metric(s)</b>	Multi-point	<b>C, n</b> , air leakage in units spec'd
<b>Acceptable Ranges</b>	Multi-point	0.45 ≤ n ≤ 1.05 r <sup>2</sup> ≥ 0.98 QP measured < reqmnt & 95% CI ≤ 8% reqmnt Largest pressure to be min 0.9 * (ΔP ref)
<b>Accepted Test Direction</b>		Depressurize, Pressurize, or Both
<b>Other</b>		Provides option for multi-zone / guarded testing

# Prepare the Building

- If the whole building is one test zone
  - Close exterior doors and windows
  - Open interior doors (security exceptions)
- Close and mask HVAC penetrations IAW Specifications
- Default HVAC Penetrations
  - All exhausts and make-up air units off
  - Motorized O/A, make-up air, exhausts and relief air dampers in closed position
  - Gravity dampers left as found (option: block closed so they do not open during test)

# Understanding Building Prep for ASTM E3158-18

Category	Envelope (Closed Up)	Operational (In Use)
Natural Ventilation openings	Sealed	Closed and latched
Active or passive smoke control systems	Sealed	As found
Waste or linen handling systems & equipment	Sealed at rooftop chute vent openings	<ul style="list-style-type: none"> <li>• Rooftop vent = open</li> <li>• Chute intake doors = closed</li> <li>• Chute intake &amp; discharge room doors = closed &amp; latched</li> <li>• Fire dampers = as fnd</li> </ul>
Interior doors, hatches, and operable windows inside the test envelope that are normally closed	Open	Closed and latched
Other interior doors	Open	Open
Mechanical ventilation or AC openings	Sealed; equipment with dampers are to have dampers closed and opening sealed	Sealed
Intermittently used mechanical ventilation or AC openings	Sealed	Sealed
Clothes dryer/vent	Sealed	As found; seal vent if dryer is not installed
Windows, doors and roof hatches	Closed & latched	Closed and latched
Solid fuel appliance (ie fireplace)	Dampers closed; chimney sealed	Dampers closed
Openings not intended for ventilation	Sealed; floor drains and plumbing traps filled	Floor drains and plumbing traps filled





- Block interior doors open
- In occupied buildings this may present an unacceptable security issue

# Identify & Seal HVAC Related Enclosure Penetrations

- Outdoor air intakes
- Exhaust systems
- Passive relief
- Steam vents
- Dampers: Motorized, gravity, none
- Fan runs continuously?
- Elevator vents and kitchen range hoods – no dampers

# Materials for Temporary Sealing

- Adhesive backed carpet protector tape
- Duct mask tape
- Garbage bags
- Light weight sheet goods and tape
- Tarps and straps
- Windex or rubbing alcohol to clean surfaces















Make sure traps have  
water in them





























# Final Review of Planning

- New, unoccupied buildings/Occupied buildings
- Identify parties
- Select date
- Identify Test Enclosure Boundaries
- Identify HVAC equipment that must be turned off and penetrations that must be sealed
- Remember Health & Safety, OSHA guidelines
- Test plan must be submitted in advance and affected parties notified

# Agenda

- Building Performance and Air Tightness
- Planning a Blower Door Test
- Running a Blower Door Test
- Interpreting Results & Building a Report



# Running a Blower Door Test

## Process

Similar to SF, software is different

- Envelope pressure measurements
- Interior pressure measurements
- Fan pressure / Flow measurements
- Distribute equipment, Central Command
- Install Fans
- Configurations
  - Tubing, Control, Communication/Network
- TECLOG

## Equipment


- Blower Door Fans & Rings
- Frames & Panels
- Controllers
- Gauges
- Tubing
- Networking/communication
- Power
- Other: Door wedges, ladders, sealing materials, tapes, mask, carpet protectors, clenaers, garbage bags

# Distribute the Equipment



# Setting up Frame and Panel

- Set up frame so it will not pop out
- Secure frame in both directions



# Setting up the Equipment

- Confirm door sizes
- Door closers / security alarms



- Prop doors open



# Install the Fans

- Pressurize or depressurize first
- Rings or caps



# Two Gauges and Three Fans

## Gauge 1

CH A: Envelope Press  
CH B: Bottom Fan

3-way Fan Control Splitter  
Connected to 3 Controllers



## Gauge 2

CH A: Middle Fan  
CH B: Top Fan



No open taps on gauges

# Tubes vs Cables

- Stepping on tubes results in pressure spikes
- Tubes of longer than 100' will cause measurement errors.
- Tubing of a smaller diameter will cause larger measurement errors.
- Sun shining on long lengths of tubing will cause errors, as will anything that causes tubing to change temperature.
- Tubing running vertically through a space at a different temperature than the rest of the building causes errors due to stack effect.

**Short tubes and long cables are best**

# Fan Speed Control: Auto Versus Manual

- Manual Control Advantages
  - Better flow precision
  - Lower current draw
  - Eliminates fan speed control cables
- Auto Control Advantages
  - Easier to hit precise targets
  - Can bring all fans up to speed together
  - Interruptions easier to deal with
  - Makes balancing pressures possible
- Hybrid Approach is also Possible



# Each fan on its own circuit

- Plug in lower fan
- Run an extension cord for the 2nd fan
- Plug volt meter into this cord
- Turn up 1<sup>st</sup> fan quickly
- If volts drops by about 2-3 volts, they are on the same circuit
- Repeat with other fans
- You can get by with 2 fans on the same circuit but make sure you have access to breaker box.
- Fans will also have less capacity – 4200 CFM75 instead of 4800 CFM75



# TECLOG & DG-1000 Networking Options

## Networking Options for DG 1000 in Single Fan and Multi-Fan Systems



### Single Fan Testing Connection Options



Bluetooth



WiFi






USB  
Micro USB



### Multi-Family, Large Building Connection Options

Multiple Multi-Fan Door – Ethernet (Wired)



Performance Testing Tools  
612.827.1117 | www.energyconservatory.com



Available from TEC Website

# Interior Pressures


- Measure to check for pressure uniformity
  - Identify Suspected Pressure Drops
  - Measure or Monitor Interior pressure differences
  - USACE and ASTM E779 require no two spaces differ by more than 10% of test pressure (wording not clear)

# Agenda

- Building Performance and Air Tightness
- Planning a Blower Door Test
- Running a Blower Door Test
- Interpreting Results & Building a Report

# Interpreting the Flow vs Pressure Graph

- Flow is on the Y-axis (Vertical)
- Envelope Pressure is on the X-axis (Horizontal)
- Plotted as Log-Log
  - Square relationship between pressure and flow means it should be a straight line on log-log plot
- Review the correlation coef.  $R$  and correlation coefficient square ( $r^2$ )
  - Higher is better. 1.0 means all the data points fall perfectly on a straight line
  - Most standards will require values greater than 0.98
- When correlation coefficients are low, it means there are some data points off the line – review graph.



Label	Base?	start	end	nobs	Avg Pressu	Total Flow
	True	83	106	24	-0.74	0
	False	160	171	12	-25.13	4988.9
	False	180	191	12	-28.45	5402.6
	False	243	254	12	-30.05	5568.9
	False	289	300	12	-35.02	6160
	False	342	353	12	-45.02	7167.6
	False	391	402	12	-50.01	7668.5
	False	431	442	12	-54.96	8056.3
	False	454	464	11	-59.96	8470.7
	False	486	497	12	-64.99	8848.4
	False	508	519	12	-70.04	9306.6

Reporting Pressure (Pa)

Test to View

**Test 1: Depressurization**

Airflow at 75 Pascals  
9736 cfm +/- 0.5 %  
Range: 9684 to 9788

Leakage Areas  
EqLA (10 Pa) = 870.6 in2 +/- 1.4 %  
ELA (4 Pa) = 489.6 in2 +/- 2.2 %

Building Leakage Curve  
Coef. (C) = 761.0 cfm/Pa<sup>n</sup> +/- 3.4 %  
Exponent (n) = .590 +/- 0.009  
Correlation Coef. (r) = .99977  
Corr Coef Squared (r<sup>2</sup>) = .99955

# How accurate does the test have to be?

- It depends:
  - Just finding holes
  - Just getting a rough idea
  - Testing to a specific leakage rate

# Sources of Uncertainty in Airtightness Testing

- Error in pressure difference across the shell
- Error in flow measurements
- Error in normalizing to volume or enclosure area
- Error in setting up building

# A Word of Advice

- Always check your data before you tear down



# Make Sure It Isn't Your Fault

- Check your data
- Compare envelope pressures
- Correct ring selection
- Correct reporting pressure
- Correct temperatures and elevation

# Compare Envelope Pressures

- On calm days the pressures should be within a couple of Pascals of each other
- On windy days there may be 20 or more Pascals difference
- Check for tubing and connection problems

# Whole Building Blower Door Testing



- Building Performance and Air Tightness
- Planning a Whole Building Blower Door Test
- Running a Whole Building Blower Door Test
- Interpreting Results & Building a Report

**Thank you**