

BUILDINGENERGY BOSTON

At the Finish Line: How Two Affordable Passive Projects Crossed the Hardest Hurdles

Michelle Apigian (ICON Architecture)

Thomas Chase (New Ecology)

Maciej Konieczny (New Ecology)

Chris Becker (Callahan Construction Managers)

Curated by Beverly Craig (MassCEC)

Northeast Sustainable Energy Association (NESEA)

February 28, 2022



2017 Passive House Design Challenge



- Up to \$4,000 per unit incentive
- 8 Affordable Projects: 540 Units
- 5 Occupied; 3 Under Construction

Incremental Cost of Achieving Passive House Standard: 2.4% average

Does not include final change orders for Kenzi and Mattapan Station; incentives not included





What are the biggest incremental costs?

- **Much better ventilation**
- **Windows and Doors**
- Efforts to reduce thermal bridging
- Higher level of construction verification

Heating and Cooling Equipment Cost Decrease:

- 6 out of 8 projects have **significantly lower size and cost for heating and cooling** equipment
- Window premium is coming way down. In some cases, cost neutral




LESSONS

- Architects with more PH training and experience had lower cost; better outcomes
- Decide early if you are seeking PH certification- if whole team on board coming out of charrette, more will go more easily
- There is a large learning curve on first PH project – expect it
- Give yourself plenty of room in PH model for things to go wrong
- All 7 of 8 projects likely to get PH certification successfully, MassSave fallback incentives still reward trying and above code outcome
- More complex roofline= more expensive

Performance: Distillery, Boston 2020


PH Uses 63% less energy per sq. ft. than median new multifamily in Boston



Data from Boston Energy Disclosure 2020 sorted for new construction multifamily built since 2010; Cross checked for LEED certification; properties with suspected lack of full building energy report are removed.

Performance: Philadelphia 2019 Affordable


PH uses 57% less energy per sq. ft. than Median Code Built



Data from Philadelphia Energy Disclosure 2019 cross checked for LIHTC multifamily; Credit to Green Building United, Katie Bartolotta

PH Performance 2019: Gilford Village Knowles III, NH

PH uses 49% less energy per sq. ft. than Gilford Village Knowles II LEED built 2008
(same building, different standard)



Graphic representation of study by Resilient Building Group (2020 Report of average 3 year energy usage data ending in 2019)



Passive House Multifamily Incentives

- 100% of feasibility study cost up to \$5,000
- 75% of PH modeling cost up to \$20,000
- \$3,000 per unit for PH certification

Current Enrollment Stats



- 116 buildings enrolled for PH incentives
- Represents 6,500+ units
- 70 buildings have completed PH feasibility studies

Passive House Education

- PH Lunch & Learns/Workshops: 59
- Total Attendees: 2,497
- PHIUS/PHI Accreditation Reimbursements: 107
- **See phmass.org video library**
- **See Passive House Accelerator videos for sessions like:
“10 Easy Ways to Ruin Your Blower Door Score (& Remedies)”**



FREE TRAINING FOR MA EMPLOYERS < 100

- Passive House Design Consultant
- Passive House Builder/Tradesperson
- LEED Green Associate Exam Prep
- Green Professional Training (GPRO)
- Intro to WELL
- Intro to Designing Net Zero Buildings
- Building Science Fundamentals



- <https://builtenvironmentplus.org/workforce-training-grants/>

Building Inherent Value:

Executing a Passive House



Presented by: Michelle Apigian AIA, LEED AP, AICP, CPHC



PASSIVE HOUSE IN ACTION

Distillery North
Finch Cambridge
Harbor Village
The Lighthouses
Hawkins


Salem Heights
Simon C. Fireman
555 Merrimack
Rindge Commons
Riverdale

Cape View Way
108 Center
Leefort Terrace
Ingalls Court
Holyoke



PERFORMANCE– Building Inherent Value

Figure 2: Source Energy Use Intensity (EUI) Comparison



Source: New York City Local Law 84 Benchmarking Report, 2013

INTENTION
TEAMWORK
INTEGRATED BUILDING SCIENCE
COMMUNICATION
CRAFT
CONFIRMATION

INTENTION

2015: MA Amendment to the IBC 2015

Accepted as Alternative Compliance path

2018: Mass CEC Passive House Design Incentives

Targeting Affordable Housing Developers

2019: Mass Save Incentives

Targets all Multifamily Developers
Builds Market-Rate attention

2020: DHCD QAP

Incentivizes Passive House above other green building standards
Catalyzes Affordable commitment to Passive House

2022: Draft Net Zero Stretch Code

Considers Passive House as a Compliance Path

Ongoing....Community Advocacy - Municipal Policy – Future Codes?

TEAMWORK

Owner

Architect

Mechanical Engineer

Structural Engineer

Energy Modeler/CPHC

Rater/Verifier

Envelope Consultant

Commissioning Agent

General Contractor

Trades

INTEGRATED BUILDING SCIENCE

Design to Drive Down Loads

Air Tightness

Continuity:

- Eliminate In/Ex-filtration
- Detail openings: windows/doors/penetrations
- Sequence Transitions

Thermal Control

Optimize

- Insulation
- Thermal bridging
- Solar heat gain

Mechanical Systems

Balanced & Decoupled

- Right Sized
- Low-Maintenance

Lighting/Appliances/ Plug Loads




Fdafd

- Efficient fixtures/appliances
- Plan for Renewables



INTEGRATED BUILDING SCIENCE

Analyze Intersections



COMMUNICATION











DESIGN INTENT

GRAPHIC
SPECIFICATIONS
ON SITE

ARTICULATE THE PRESSURIZED BOUNDARY


















COMPARTMENTALIZATION LEGEND

NOTE: DRAWINGS A-119 THRU A-133 & A-303 SHOULD BE PRINTED IN COLOR

| | |
|---|--|
|  | COMPARTMENTALIZED SPACE. SEE SPEC SECTION 3.13 OF 092110 |
|  | CONTINUOUS AIR BARRIER |
|  | CONTINUOUS THERMAL & AIR BARRIER |
|  | UNCONDITIONED SPACE OUTSIDE PASSIVE HOUSE ENCLOSURE |
|  | CONDITIONED SPACE OUTSIDE PASSIVE HOUSE ENCLOSURE |
|  | INSULATION |
|  | SPRAY FOAM INSULATION |
|  | RIGID INSULATION |
|  | CONTINUOUS EXTERIOR INSULATION: MINERAL WOOL |
|  | FIBERGLASS INSULATION |


AIRTIGHTNESS DETAILS LEGEND

NOTE: DRAWINGS A-119 THRU A-133 & A-303 SHOULD BE PRINTED IN COLOR


| | |
|---|---|
| PEEL/STICK APPLIED CONT. AIR BARRIER | |
|  AB-1A | BLUESKIN VP-160 (VAPOR OPEN) |
|  AB-1B | BLUESKIN SA (VAPOR CLOSED) |
| POLY AIR BARRIER | |
|  AB-2A | VIPER II 10 MIL VAPOR BARRIER (VAPOR CLOSED) |
|  AB-2B | VIPER II PENETRATION BOOT (VAPOR CLOSED) |
|  AB-2C | UNDER SLAB OR ROOF VAPOR BARRIER (VAPOR CLOSED) |
|  AB-2D | ROOF VAPOR BARRIER (SMART BARRIER) |
|  AB-3 | FULLY GROUTED CMU OR CONC. AS AIR BARRIER. SEAL HOLES WITH BLUESKIN BES 925 |
| CLOSED CELL SPRAY FOAM MIN R-30 | |
|  AB-4 | HIGH LIFT SPRAY FOAM WITH FLAME BLOCK (VAPOR CLOSE) |
| CRYSTALLINE WATERPROOFING | |
|  AB-5 | XYPEX (VAPOR CLOSED) |
| FLUID APPLIED AB | |
|  AB-6A | BLUESKIN AIRBLOCK 17 (VAPOR OPEN) |
|  AB-6B | BLUESKIN CM-100 (VAPOR CLOSED) |
| FIRESTOPPING | |
|  AB-7 | HILTI FIRESTOP SYSTEMS |
|  C | SERVICE CHASE |
|  D | SHEATHING - PLYWOOD AT 3A CONSTRUCTION, DENSGLOSS AT 1A CONSTRUCTION |
|  E-1 | AIRTIGHT DOORS |
|  E-2 | AIRTIGHT FIRE RATED DOORS |
|  F | PIECE IN SHEATHING/GWB FOR PROPER CONTINUITY & SEQUENCING |
| NUMBERS NOTATED INDICATE CONSTRUCTION SEQUENCE | |

COMPARTMENTALIZATION NOTES

1. PROVIDE SEALANT BETWEEN GWB AND TOP/SILL PLATES AS WELL AS BETWEEN STUD FRAMING AND GWB AT OPENINGS (DOORS, WINDOWS, HVAC UNITS, ETC.). SEAL PERIMETER OF ELECTRICAL/TELE-DATA BOXES (OUTLETS, LIGHTS, SWITCHES, ETC.) IN WALLS AND CEILINGS. ELECTRICAL BOXES ARE TO BE 'AIR SEALED' BOXES AND SEALING OF BOX PENETRATIONS SHALL BE AS SPECIFIED.
2. AT DEMISING WALLS (UNIT-TO-UNIT, UNIT-TO-CORRIDOR, AND UNIT-TO-COMMON AREA), PROVIDE INTERIOR AIR BARRIER (AIRSEALING). PROVIDE SEALANT AS SPECIFIED BETWEEN SILL PLATE/TOP PLATE AND GWB, TYPICAL.



2 GROUND/ FIRST FLOOR COMPARTMENTALIZATION
1/16" = 1'-0"



1 Garage Level Compartmentalization
1/16" = 1'-0"

ARTICULATE TRANSITIONS (including sequence)

COMPARTMENTALIZATION LEGEND

NOTE: DRAWINGS A-119 THRU A-123 & A-203 SHOULD BE PRINTED IN COLOR









-  COMPARTMENTALIZED SPACE (SEE SPEC SECTION 5.13 OF 092111)
-  CONTINUOUS AIR BARRIER
-  CONTINUOUS THIRIMA & AIR BARRIER
-  UNCONDITIONED SPACE OUTSIDE PASSIVE HOUSE ENCLOSURE
-  CONDITIONED SPACE OUTSIDE PASSIVE HOUSE ENCLOSURE
-  INSULATION
-  SPRAY FOAM INSULATION
-  INSULATION
-  CONTINUOUS EXTRUSION POLYURETHANE FOAM
-  BRICK/CLAY
-  FIBROGLASS INSULATION










COMPARTMENTALIZATION NOTES




- 1 PROVIDE SEALANT BETWEEN DMB AND TOPBILL PLATES AS WELL AS BETWEEN STUD FRAMING AND DMB AT OPENINGS (DOORS, WINDOWS, HVAC UNITS, ETC.). SEAL PERIMETER OF ELECTRICAL/TELE. DATA BOXES (OUTLETS, LIGHTS, SWITCHES, ETC.) IN WALLS AND CEILINGS. ELECTRICAL BOXES ARE TO BE AIR SEALED. BOXES AND SEALING OF BOX PENETRATIONS SHALL BE AS SPECIFIED.
- 2 AT DEMISING WALLS (UNIT TO UNIT, UNIT TO CORRIDOR, AND UNIT TO COMMON AREA), PROVIDE INTERIOR AIR BARRIER (AIR SEALING). PROVIDE SEALANT AS SPECIFIED BETWEEN SILL PLATE/TOP PLATE AND DMB, TYPICAL.
- 3 SEE 204.106 FOR DETAIL OF DEMISING WALL AT EXTERIOR WALL.
- 4 SEE DETAIL 2 & 3 ON A406 FOR DETAIL AT FLOOR.






AIRTIGHTNESS DETAILS LEGEND

NOTE: DRAWINGS A-119 THRU A-123 & A-203 SHOULD BE PRINTED IN COLOR

-  FEELSTICK APPLIED CONT. AIR BARRIER
-  SLAB MAJEST 250 SA (VAPOR OPEN) USE SIGA WELLYV TAPE AT VERTICAL BEAMS
-  SIGA FENTRIM TAPE (VAPOR OPEN)
-  POLY AIR BARRIER
-  NO LONGER USED
-  SLAB VAPOR BARRIER (VAPOR CLOSED)
-  ROOF VAPOR BARRIER (SMART-BARRIER)
-  MASTIC AIR BARRIER


-  FULLY UNDATED DMB OR CONC. AS AIR BARRIER
-  CLOSED CELL SPRAY FOAM (MIN-F-30)
-  HIGH LET. SPRAY FOAM WITH FLAME BLOCK (VAPOR CLOSED)
-  CRYSTALLINE WATERPROOFING
-  XYPEX (VAPOR CLOSED)
-  FILLED APPLIED AIR
-  BULLSEYE CM-100 (VAPOR CLOSED)
-  FIRESTOPPING
-  MULTI-FIRESTOP SYSTEMS

-  TARED SHEATHING AS AB
-  ROOF SHEATHING TAPED AT ALL SEAMS
-  SHEATHING OR RIGID INSULATION TAPED AT ALL SEAMS WITH SIGA AIRBARRIER TAPE (RUBBER-BASED TAPE RECOMMENDED)

-  SHEATHING - PLYWOOD AT 1A CONSTRUCTION
-  DENSO GLASS AT 1A CONSTRUCTION
-  AIRTIGHT DOORS
-  AIRTIGHT FIRE RATED DOORS
-  PIECE IN SHEATHING/CWIS FOR PROPER CONTINUITY & SEQUENCING

COMPARTMENTALIZATION DETAIL NOTES

- 1 TAPE ALL INTERSECTIONS BETWEEN AIR BARRIER AND ANOTHER MATERIAL.
- 2 PENETRATIONS AT AIR BARRIERS SHOULD BE FULLY FIRE STOPPED AND AIRTIGHT.



COMMUNICATION – Speaking the same Language



3 Week Look Ahead Schedule


Job Number: 19-005001
 Project Name: 206 Main Street Gloucester
 Superintendent: Keith Mareszka

Date: 4/13/2020
 Start Date: 4/13/2020
 End Date: 5/3/2020
 Project Executive: Dave Groom
 Project Manager: Matt Robbins

Entering S, B or X will shade cell automatically
 Scheduled Behind Schedule X Will shade cell black

***Subcontractors must notify Groom Construction Project Manager or Superintendent within 24 hours of receiving this Three Week Look Ahead Schedule if not able to meet this schedule.

| Item/Task | Subcontractor | Week #1 | | | | | | | Week #2 | | | | | | | Week #3 | | | | | | | Remarks/Notes | | |
|---|--------------------|---------|------|------|------|------|------|------|---------|------|------|------|------|------|------|---------|------|------|------|-----|-----|-----|---------------|--|----------------------|
| | | M | T | W | Th | F | Sa | Su | M | T | W | Th | F | Sa | Su | M | T | W | Th | F | Sa | Su | | | |
| | | 4/13 | 4/14 | 4/15 | 4/16 | 4/17 | 4/18 | 4/19 | 4/20 | 4/21 | 4/22 | 4/23 | 4/24 | 4/25 | 4/26 | 4/27 | 4/28 | 4/29 | 4/30 | 5/1 | 5/2 | 5/3 | | | |
| BUILD ELECTRICAL ENCLOSURE FOR TEMP POWER | GROOM | S | | | | | | | | | | | | | | | | | | | | | | | |
| FORM WALLS HH LINE | FORM UP | S | S | S | | | | | | | | | | | | | | | | | | | | | MONDAY IS A RAIN OUT |
| FORM FOR PAD AT STAIR # 2 | FORM UP | S | S | S | | | | | | | | | | | | | | | | | | | | | |
| RECEIVE REBAR | GROOM | S | | | | | | | | | | | | | | | | | | | | | | | |
| INSTALL DRAINAGE | LINSKEY | S | S | S | S | S | | S | S | | | | | | | | | | | | | | | | |
| FINISH DIGGING FOR FOOTING AT A LINE | LINSKEY | | S | | | | | | | | | | | | | | | | | | | | | | |
| FORM FOOTING AT A LINE | FORM UP | | S | S | | | | | | | | | | | | | | | | | | | | | |
| POUR THE REST OF THE FOOTING ON A LINE | FORM UP | | | S | | | | | | | | | | | | | | | | | | | | | |
| POUR PAD FOR STAIR # 2 | FORM UP | | | | S | | | | | | | | | | | | | | | | | | | | |
| REMOVE FORMS AT FOOTINGS AND PAD | FORM UP | | | | | S | | S | | | | | | | | | | | | | | | | | |
| BACK FILL 1/2 OF THE WALL ON 7 LINE | LINSKEY | | | | | | | | | S | S | | | | | | | | | | | | | | |
| FORM WALL ON A LINE | FORM UP | | | | | | | S | S | S | | | | | | | | | | | | | | | |
| POUR WALL ON A LINE | FORM UP | | | | | | | | | S | | | | | | | | | | | | | | | |
| START CMU STAIR # 2 | VAZ | | | | | | | | | S | S | | S | S | S | S | S | | | | | | | | |
| FINISH DIGGING HH LINE FOR FOOTINGS , FORM AND POUR FOOTING HH LINE | LINSKEY AND FORMUP | | | | | | | | | | | | | | | S | S | | | | | | | | |
| POUR THE REST OF FOOTING ON HH LINE | FORM UP | | | | | | | | | | | | | | | | S | | | | | | | | |
| HOPE FOR TEMP POWER | GROOM | | | | | | | | | | | | | | S | S | S | S | | | | | | | |



Harbor Village
 206 Main Street,
 Gloucester, MA

DATE:

BY:

SCALE:



| | |
|-----------|-----------------------|
| DATE | DESCRIPTION |
| OCT 2018 | PERMIT SET |
| 07/1/2019 | FINAL STOP SUBMISSION |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |

PROJECT NUMBER: Project Number:
 DRAWN BY: Author
 CHECKED BY: Checker

10/25/18 12/18/18

GROUND LEVEL PLAN

LOOK AHEAD

1. FOUNDATION: WATERPROOFING

2. STEEL POSTS

3. CMU WALLS


4. INTUMESCENT PAINT ON STEEL AS AIR BARRIER

5. SUB GRADE INSULATION MIN 48" BELOW GRADE


6. SUB SLAB INSULATION, VAPOR BARRIER, LAPS UP, SLAB POURED

7. AIR BARRIER ON CMU, LAP VAPOR BARRIER, INTUMESCENT PAINT ON STEEL & FOUNDATION WATERPROOFING & SPRAY FOAM UNDERSIDE OF DECK




8. INSULATION ABOVE GRADE, & SPRAY FOAM UNDERSIDE OF DECK




3/A116



DO WE NEED?



TAPE TRANSITION
4' BELOW GRADE



LOBBY SEQUENCE

1. FOUNDATION:
WATERPROOFING

2. STEEL POSTS

3. STRUCTURAL
CMU WALLS


4. INTUMESCENT
PAINT &
STRUCTURAL
THERMAL BREAKS

5. STRUCTURAL
THERMAL BREAKS

6. VERTICAL
SUB GRADE

7. SUB SLAB
INSULATION

8. VAPOR BARRIER, LAPS
UP, SLAB POURED




9. AIR BARRIER ON CMU


10. METAL STUDS AND NON
STRUCTURAL CMU WALLS
WITH AIR BARRIERS

11. INSULATION ABOVE
GRADE, & SPRAY FOAM
UNDERSIDE OF DECK

DETAILS AT DOORS



2 PASSIVE HOUSE DOOR MTL JAMB DETAIL
3" = 1'-0"



1 PASSIVE HOUSE SILL DETAIL @ SLAB ON GRADE
3" = 1'-0"

INVEST IN CRAFT

ON SITE COMMUNICATION

SCHEDULE SEQUENCE TRADES

- Carpenters
- Insulators
- Plumbers
- HVAC Installers
- Electricians

Craft – Envelope Airtightness Continuity

Caio's Team
rocking the
Air Barrier



Craft: Pipe/Penetration Airtightness



First Try – Not Approved




Ian Russell - Plumber



Second Try – Approved

CRAFT- HVAC



CRAFT– Electrician




Not Approved



Approved



Not Approved



Approved

CONFIRMATION: TESTING/VERIFICATION

REGULAR INSPECTIONS

INFRARED

BLOWER DOOR TESTING

& TROUBLESHOOTING



COMMISSIONING

TESTING/VERIFICATION

Windows
Airtightness
Duct Leakage
Thermal Bridging/Gaps



| | |
|---|------------------------------|
| .6 ACH₅₀ | 2611 CFM₅₀ |
| <u>DUCLOS METHOD RECOMENDATIONS</u> | |
| Stage #1 Test (envelope no windows & Doors) | 652.75 CFM ₅₀ |
| Stage #2 Test (windows & doors) | 1552.75 CFM ₅₀ |
| Stage #3 Test (MEP penetrations) | 2219.35 CFM ₅₀ |




CONFIRMATION: TROUBLE SPOTS

BLOWER DOOR TESTING



Adiabatic Transitions

Compartmentalization









TEAMWORK

Owner

Architect

Mechanical Engineer

Structural Engineer

Energy Modeler/CPHC

Rater/Verifier

Envelope Consultant

Commissioning Agent

General Contractor

Trades

Michelle Apigian

AIA, LEED AP, AICP, CPHC

Associate Principle, Practice + Sustainability Leader

mapigian@iconarch.com

627-939-0721





LESSONS LEARNED

Whole Building Air Tightness: Harbor Village




WBBD Test Protocol

- **Testing Standard**
ASTM E779
- **Testing Preparation**
Appendix F - ANSI/RESNET/ICC 380-2016: Procedure to Prepare the Building for Testing
Phius Variance – Barometric/spring-loaded dampers to be sealed in the direction of the test for which they will be force-failed open. Fresh air intake dampers sealed during depressurization, exhaust dampers to be sealed during pressurization.
- **Results Reporting**
Report both pressurization and depressurization testing, final result is average of the two.
Pass-fail air infiltration target test.
WUFI model test (can exceed pass-fail threshold, provided energy model results to not exceed threshold metrics).
- **Best Practices for Mid-Point and Final Testing**
Test plan with: site information, testing and site staff contacts, building control plan, test type and targets, equipment list, building preparation protocol, temporary air sealing checklist, and schedule.



Allowable Effective Leakage Area



Effective Leakage Area vs. Total Enclosure Area

34,600 ft²


WBBD Results – Midpoint to Final

| Date | CFM50 (depress.) | CFM50 (press.) | CFM50 (avg.) | ACH50 |
|---------|---------------------|-------------------|--------------|-------|
| 2/26/21 | 5,486 | - | - | 1.44 |
| 5/14/21 | 4,233 | - | - | 1.11 |
| 6/4/21 | 3,288 | - | - | 0.86 |
| 7/8/21 | 2,850 | - | - | 0.75 |
| 7/26/21 | 1,953 | 2,190 | 2,072 | 0.54 |


What Worked



2/26/2021 – Midpoint 1




5/14/2021 – Midpoint 2



7/8/2021 – Midpoint 4



7/26/2021 - Final



Other Approaches to Try



Squirrelwood Across the Finish Line – PH Lessons



Squirrelwood - Speakers and Team

Callahan training



Maciej Konieczny
CPHC/B, CEM, LEED AP BD+C, Homes
Senior Project Manager
konieczny@newecology.org
617-557-1700 x7024



Chris Becker
CPHB
Project Manager
cbecker@Callahan-inc.com
508-443-2381




- | | |
|---------------------------|--|
| Owner: | Just-A-Start Corporation Cambridge, MA |
| General Contractor | Callahan Construction Managers Bridgewater, MA |
| Architect: | Davis Square Architects Somerville, MA |
| Civil: | Devellis Zrein, Inc. Foxborough, MA |
| Structural: | Dan Bonardi Consulting Engineers Arlington, MA |
| MEP: | BLW Engineers, Inc. Littleton, MA |
| Sustainability: | New Ecology, Inc. Boston, MA |
| BECx | Building Enclosure Associates Boston, MA |

SQW – Objectives

Agenda:

- Project Summary
 - PHIUS targets
 - Envelope, Systems
- Process Review
 - Design and pre-construction services
 - Start of construction/training
 - Mock-up
 - Collaboration
- Construction
 - Challenges and Solutions - Examples
- Q+A



SQW – Project Summary

- Owner/Developer: Just-A-Start
- 14 affordable family units
- PHIUS+ 2015
- iCFA: 13,400 ft²
- Opening Fall 2021





| | Target | Modeled |
|---|------------------------------------|----------------------|
| Heating Demand; kBtu/ft ² yr | 5.3 | 3.11 |
| Cooling Demand; kBtu/ft ² yr | 2.9 | 1.59 |
| Heating Load; Btu/hr | 4.4 | 3.21 |
| Cooling Load; Btu/hr | 4.2 | 2.49 |
| Source Energy; kWh/yr | 6,200 | 5,541 |
| Air Tightness | 0.05 cfm/ft ² (971 cfm) | 653 cfm (0.27 ACH50) |

3rd tightest MF building in US, excluding THs

SQW – Envelope

- Double studded wall
 - 2x6 structure; 1" space; 2x4 interior wall
 - Staggered studs, 24" O.C. as allowed
 - 3" CCSF inc. studs + 7" Cellulose
 - Siga AWB

- Windows
 - Triple Pane; clips
 - Insulated Headers
 - Siga Wigluv flashing



REPT
OTES



SQW – Envelope

Roof:

- 2" min Polyiso above roof deck
- 20" Truss depth with 4" of CCSF
- 16" cellulose

Foundation/Slab

- 5" EPS sub-slab insulation
- 15 mil Steggo Wrap VB taped to Siga WRB
- 2x2" EPS foundation



SQW – Systems

Ventilation:

- Ventacity VS1000;
- 82% Eff; 0.61 W/CFM
- 850 CFM

DHW:

- Instantaneous Electric
- Stiebel Eltron

Heating/Cooling


- Mitsubishi SUZ-KA HPs



SQW – Process

Design and pre-construction services

- Commit to PH early
- Include GC at DD or earlier
- Schedule multiple integrated design meetings
- Submit project to PHIUS at ~50% DD for Round 1 review
 - Experienced energy modeler is critical
- CPHC to participate in VE
- Use color in drawings



SQW – Process - Training

Start of construction/training

- Reach out to GC before kick off
- Include PHIUS verifier, BECx
- Foremen of each trade required
- Involve subs in motivation behind the PH goal
 - People like to understand what and why?
- Focus meeting on working through details
- **Collaborate** – NOT just a lecture

Collaboration

- Between design and construction teams
- Between GC and sub contractors
- GC and Subs are very knowledgeable even if this is their first PH
- Listen to constructability suggestions



Passive House Orientation Construction Squirrelwood – Building L

February 14, 2019



SQW – Process – Mock-Up

Dedicated Mock-Up

- Most important stage of construction Assume multiple visits from CPHC and BECx
- Bring window and AWB manufacturer on site
- Identify critical details and transitions:
 - Foundation/slab/wall
 - Wall: AWB/insulation, inside/outside corners
 - Window flashing/install
 - Wall/Roof transition
 - MEP Penetrations
 - Doors –Leave up until building reaches the same level of completion
- COLLABORATE



SQW – Process – Mock-Up



Require proper tools




Document each step



Involve all related subs

SQW – Process – Mock-Up



Pay attention to details and adjust as needed



Track the details




Finalize and confirm approach



Leave up until installed in situ



SQW – Challenges and Solutions

Detail created after design – PREPRUFE membrane and mat slab required due to high water table.



SQW – Challenges and Solutions

VB to AWB Continuity





SQW – Challenges and Solutions

Awkward transition for AWB



SQW – Challenges and Solutions

Challenging AWB transition




Vapor Barrier @ M - Slab on Grade at Wood

Vapor Barrier @ L - Slab on Grade at Wood



SQW – Challenges and Solutions




QUESTION

During our Passive House meeting on 12/4/19, we reviewed the TIM Bearing pad on detail G9/A530. There is a space above the bearing pad that is not marked. Please advise what this material is. Also, the vapor barrier was discussed and the TIM bearing pad's penetration through the vapor barrier in (4) locations. After review with New Ecology and Bridgeline we agreed the best way to maintain the vapor barrier in these locations is going to be by caulking the TIM bearing pad making it part of the vapor barrier. Please confirm this is acceptable in these (4) locations.

SQW – Challenges and Solutions

Maintain unit compartmentalization




A-9 DETAIL AT EXT. ENTRY DOOR HEAD

1 1/2" = 1'-0"



SQW – Challenges and Solutions



QUESTION

During our Passive House meeting on 12/4/19, we reviewed the vapor barrier in detail A1/A540. Per our discussions, the way the vapor barrier is currently drawn would not be constructible. Reviewing with New Ecology, Bridgeline, and Max Sontz roofing, we propose to add plywood to the bottom of the soffit (green), and have the vapor barrier (red) run on the outside of the soffit as show in the attached. The trim on the exterior would need to be larger to account for the depth of the plywood and create the same profile as the original design. Please confirm this approach is acceptable.

SQW – Challenges and Solutions

QUESTION

...



SQW – Challenges and Solutions

QUESTION

...



SQW – Challenges and Solutions

Thermal Insulating Pads



SQW – Challenges and Solutions

Polyethylene Suspension
work – insulation should
– find correct photo
Find insulated pipe ha
like rain leaders



SQW – Challenges and Solutions

GC Quality Control – Punchlist by trade

#55 General

Status
Open

Type
Issue

Description
Patch and seal around on
Over cut electrical boxes

Created
Nov 18, 2020 2:07 PM
sbartley@callahan-inc.com

Last Updated
Nov 18, 2020 2:07 PM

Sheet
4 Punchlist Third Floor



Photos



20201118_104610_photo
Steve Bartley
Nov 18, 2020 10:46 AM



20201118_104559_photo
Steve Bartley
Nov 18, 2020 10:46 AM

#213 General

Status
Open


Type
Issue

Description
Seal all penetrations

Created
Nov 19, 2020 1:51 PM
sbartley@callahan-inc.com

Last Updated
Nov 19, 2020 1:51 PM

Sheet
2 Punchlist First Floor



Photos



20201119_114002_photo
Steve Bartley
Nov 19, 2020 11:40 AM

SQW – Challenges and Solutions

QUESTION

...

#210 Plumbing

Status

Open

Type

Issue

Description

Seal all plumbing penetrations below

Created


Nov 19, 2020 1:50 PM
sbartley@callahan-inc.com

Last Updated

Nov 19, 2020 1:51 PM

Sheet

2 Punchlist First Floor



Photos



20201119_113740_photo
Steve Bartley
Nov 19, 2020 11:37 AM



20201119_113716_photo
Steve Bartley
Nov 19, 2020 11:37 AM

#182 Duct Work

Status

Open

Type

Issue

Description

Seal all ductwork

Created

Nov 19, 2020 1:45 PM
sbartley@callahan-inc.com

Last Updated

Nov 19, 2020 1:45 PM

Sheet

2 Punchlist First Floor



Photos



20201119_110314_photo
Steve Bartley
Nov 19, 2020 11:03 AM



20201119_110246_photo
Steve Bartley
Nov 19, 2020 11:03 AM

SQW – Challenges and Solutions

Ventilation testing ... and failure.



Squirrelwood Bldg L Ventilation

| | SUPPLY | | | EXHAUST | | |
|--------------|-------------|------------|------------|-------------|------------|-----------|
| | Unit Design | Flow | Delta | Unit Design | Flow | Delta |
| TOTAL | 850 | 724 | 15% | 850 | 845 | 1% |

| | | |
|------------|------------|------------|
| 724 | 845 | 14% |
| 764 | 845 | 10% |

CFM of Supply needed to get within 10%

40


CFM of Supply per unit need to get within 10%

3

SQW – Challenges and Solutions

AeroSeal –

- Saves time and hassle
- Include on every project



<https://makeitright.ca/holmes-advice/home-renovation/aeroseal-the-new-way-to-duct-sealing/>





DUCT SEALING REPORT

| Duct Sealing Performed For: | | | | | | | | | | | | | | | | | |
|---|--|------------------------|-----------------------|---|-------|---|-----|----|-----|----|-----|----|----|----|----|----|---|
| Squirrelwood Apartments 281 Broadway St Cambridge, MA 02139 | AEROSEAL CASE ID: 3068 SYSTEM DESCRIPTION: Central Rooftop ERV SEAL DESCRIPTION: Sealing Main, 1st, 2nd and Basement Exhaust HARDWARE: Gen2 TECHNICIAN: R Gomez | | | | | | | | | | | | | | | | |
| DATE: 04/2021 | | | | | | | | | | | | | | | | | |
| Overall Sealing Results: | Aeroseal Sealing Progress: | | | | | | | | | | | | | | | | |
| BEFORE SERVICE 774.7 CFM of Leakage, equivalent to a 36.8 Square Inch Hole or 0.00% of the system capacity of 0.0 CFM | <table border="1"> <caption>Aeroseal Sealing Progress Data</caption> <thead> <tr> <th>Sealing Time (Minutes)</th> <th>CFM Leakage at 1 w.g.</th> </tr> </thead> <tbody> <tr><td>0</td><td>774.7</td></tr> <tr><td>5</td><td>600</td></tr> <tr><td>10</td><td>300</td></tr> <tr><td>15</td><td>150</td></tr> <tr><td>20</td><td>50</td></tr> <tr><td>25</td><td>10</td></tr> <tr><td>30</td><td>5</td></tr> </tbody> </table> | Sealing Time (Minutes) | CFM Leakage at 1 w.g. | 0 | 774.7 | 5 | 600 | 10 | 300 | 15 | 150 | 20 | 50 | 25 | 10 | 30 | 5 |
| Sealing Time (Minutes) | | CFM Leakage at 1 w.g. | | | | | | | | | | | | | | | |
| 0 | | 774.7 | | | | | | | | | | | | | | | |
| 5 | 600 | | | | | | | | | | | | | | | | |
| 10 | 300 | | | | | | | | | | | | | | | | |
| 15 | 150 | | | | | | | | | | | | | | | | |
| 20 | 50 | | | | | | | | | | | | | | | | |
| 25 | 10 | | | | | | | | | | | | | | | | |
| 30 | 5 | | | | | | | | | | | | | | | | |
| AFTER SERVICE 29.0 CFM of Leakage, equivalent to a 1.4 Square Inch Hole or 0.00% of system capacity | | | | | | | | | | | | | | | | | |
| This corresponds to a 96% Reduction in Duct Leakage | | | | | | | | | | | | | | | | | |
| NOTE: Duct leakage results are calculated in Cubic Feet per Minute (CFM) measured at a STANDARD OPERATING PRESSURE of 1 w.g. | | | | | | | | | | | | | | | | | |
| Duct Sealing Performed By: | | | | | | | | | | | | | | | | | |
| <input checked="" type="checkbox"/> | Aspen Air Duct Cleaning 270 Lawrence St. Methuen, Ma 01844 Phone: 978-681-5023 | | | | | | | | | | | | | | | | |

Aeroseal process uses DuctSeal sealant that is certified to meet requirements listed in UL 1318 standard "Outline of Investigation for Aeroseal Duct Sealant". Please provide Aeroseal feedback at <http://bit.ly/2021aeroseal> and reference code TR0000129.


SQW – Challenges and Solutions

Even with open corner framing, insulation had to be fixed in some locations
- Continuous QC



SQW – Challenges and Solutions

Window testing – in situ and early
- Consider test on mock-up




TEST RESULTS

Air Infiltration Tests, ASTM E783

| | | <u>Specimen Number:</u> | | |
|------------------------------|-------------------------------------|-------------------------|----------|----------|
| | | <u>1</u> | <u>2</u> | <u>3</u> |
| <u>Testing</u> | <u>Specifications</u> | | | |
| | a) Pressure differential, psf: | 6.24 | 6.24 | 6.24 |
| | b) Pressure differential, Pa: | 298.7 | 298.7 | 298.7 |
| | c) Allow infiltration rate, cfm/sf: | 0.15 | 0.15 | 0.15 |
| <u>Measured Results</u> | <u>Air Flow</u> | | | |
| | d) Specimen, total square feet: | 12.0 | 15.0 | 15.0 |
| | e) Total, cfm: | 12.75 | 9.0 | 7.0 |
| | f) Extraneous, cfm: | 12.25 | 8.25 | 6.0 |
| | g) Specimen, cfm (g=e-f): | 0.5 | 0.75 | 1.0 |
| | <u>Rate</u> | | | |
| | h) Total, cfm/sf (h=e/d): | 1.06 | 0.60 | 0.46 |
| i) Specimen, cfm/sf (i=g/d): | 0.04 | 0.05 | 0.07 | |

SQW – Challenges and Solutions

Envelope Testing – Passed – first attempt.



THANK YOU.



Maciej Konieczny
CPHC/B, CEM, LEED AP BD+C, Homes
Senior Project Manager
konieczny@newecology.org
617-557-1700 x7024



Chris Becker
CPHB
Project Manager
cbecker@Callahan-inc.com
508-443-2381



Take Aways

- Make it a conversation, not a lecture.
- Learn from others.
- There is a big learning curve on the first one: expect it!
- Test and inspect early and often, especially on the first one.
- Invest in Craft – every trade is ready to execute, if empowered & given the tools