

project stats

Location: Madison WI

Dwellings: 32 (qty 22 1-bed, qty 10 2-bed)

Parking: 32 (4 EV chargers, 8 EV ready)

Gross Area (w/ parking): 44,810 sf

Gross Area (w/out

parking): 32,088 sf

Envelope Area: 40,518 sf

Blower door: 0.057 cfm/sf @50 pascal!

Hard cost: \$8.33M / \$8.48M (actual / budget)

Construction schedule: 12 months (appx.)

Leasing: Stabilized in 3 months!

Phius: Phius CORE 2021

Notable Building Partially below-grade parking

Attributes: garage, partial green roof, ballasted roof mount solar

system






making it happen

Rigorous evaluation of envelope and systems in the face of a predetermined, already approved design and complex entitlement processes

Creative financing strategies that leveraged equity to add value and align stakeholders

Careful communication with stakeholders and project team – all-in approach

Eliminating 'fear' – related pricing escalation by identifying critical team members and shifting passive building-related scope and responsibility to high performance envelope / oversight role



Phius Awards

252 Dunning

with the designation of a Phius Certified Project



Project Address 2165 Linden Avenue

Madison, Wisconsin 53704

Program Version Phius CORE 2021

Project Number 2210

Certification Date 09/26/2025

Architecture Planning Knothe Bruce Architects

Building Owner Threshold Equity

Construction Company Krupp General Contractors

Mechanical Systems Designer Staegl Engineering and Harker Heating and Cooling

Lead Phius CPHC® Timothy McDonald
Phius Certified Verifier David M Horton


Phius CPHB Sean Size





if you make it, you own it.

RESPONSIBILITY FOR QUALITY AND EXECUTION, ATTENTION TO DETAIL, EMPOWERMENT THROUGH CONTRIBUTION, ACCOUNTABILITY THROUGH COLLABORATION ----- EVERY DETAIL COUNTS





navigating entitlements

certification as a pre-requisite to building permits

1

PROJECT TIMELINE

2020

Zion Lutheran leaving urban site (combining to form Common Grace). Initial attempts by affordable housing developer stalls, is not feasible. Begins relationship with Threshold Development Group – uninspired luxury condominiums, not well-received. Development requires a Planned Development rezoning.

2020 - 2021

Design alternatives – move to rental concept (42 units proposed)

January - April 2022

UDC informational and initial

January - May 2022

Demolition permit, neighborhood plan amendment, rezoning to PD, CSM (plan commission / common council) *Condition of Approval: Phius Design Certified

January 2023

UDC Final approval

January 2023 - July 2023

Design development, construction documents, and bidding = over budget

August 2023 - October 2023

Value management, rebidding, GMP

November 2023 - May 2024

OAC meetings and passive building optimization meetings continue Early-Start Permit May 15, 2024 – Phius Design Certified Condition*

Footings and foundation, and pre-cast + topping

May 2024 to August 2024

Phius Design Certified (targeting 8/2/2024 vertical construction to maintain schedule)

- HVAC
- Plumbing
- WUFI back and forth
 Phius Design Certified 6/28/24
 Site Plan Review + PD Recording

August 2024 - May 2025

Construction and QA/QC

May 2025 - August 2025

Leasing and stabilization

July – August 2025

Phius Verifier final submission / documentation

September 2025

Phius Final Certification!



certification as a pre-requisite to building permits

LESSONS LEARNED

Commit to Phius certification once the building is already designed and has begun design review / public hearings

Phius Design Certified – Condition of Approval (building permit)

- Design-build prime subs conventional
- Fast-track typically MEP trails building permit
- Phius Design Certification requires thorough QA/QC process to confirm the as-designed building is certifiable
- Construction start
 - -Early-start permit (to precast with topping)
 - -Full building permit received truly JIT
- Plumbing
 - -WI Code vs IAMPO oversized distribution system
 - -Complex domestic hot water
- HVAC straightforward but still unique ducting challenges



06/27/2024

To whom it may concern,

Congratulations! We are pleased to inform you that **2210 - 2165 Linden Avenue** is now a Design Certified **Phius CORE 2021** project.

Thank you for choosing Phius and best wishes to your team on achieving Certification. Please contact us when commissioning is complete and you are ready for Certification review, or earlier if you have any other issues to discuss.

Regards,

James Ortega, Certification Program Director

Phius Certification Team

Isaac Elnecave, Haley Kalvin-Gold, John Loercher, Shannen Martin, Al Mitchell, Andrés Pinzón [PhD], Zoe Rader, Neil Rosen, Aditya Singh, Mark Smith

Phius | Passive House Institute US

53 W. Jackson Blvd. Suite 1432 Chicago, Illinois 60604 | 3125614588 www.phius.org

'business as usual' approach with integration of high performance systems

INCORPORATING MEP DESIGN / BUILD WITH PASSIVE BUILDING PROCESSES

MEP design / build is typical for this scale / use / market / location...so why change now?


Inherent complexities of pursuing Design Certification when the EOR isn't formally engaged

Passive building holistic overview via energy modeling points towards having systems fully designed / more traditional design / bid / build model

Long lead items in passive building (ie windows) need to be ordered before engineered designs are finalized

EOR in design / build is often yet another subconsultant of the Primary Subcontractor – one more layer of removal from the passive design team / process

Basis of Design with passive building-focused MEP becomes critical to staying on track





'business as usual' approach with integration of high performance systems

KEEP THE COMPONENTS SIMPLE

System / Components aren't anything too complicated or foreign:


Heating / cooling via decentralized air source heat pumps, mostly ducted with select non-ducted

Domestic hot water via centralized Sanco CO2 refrigerant heat pump system

Individual, in-unit ERVs

Infrastructure for future in-unit dehumidifiers


Critical feedback / input from Basis of Design essential for coordinating with EOR and the subcontractor



passive building as a new concept


new assemblies, new priorities, and real performance targets





LEARNING CURVES / CHALLENGES

- A. Limited ability to impact physical design, which was previously approved prior to passive building goal adoption
- B. Passive building over tempered parking garage condition
- C. Continuous air-control layer: basic for a passive building, but not necessarily top of mind for a conventional build
- D. Continuous insulation: not yet everyday detailing in this market / location



new assemblies, new priorities, and real performance targets

LIMITED ABILITY TO IMPACT PHYSICAL DESIGN

No permitted changes from approved plans; form, density, unit layout to remain as originally approved (pre-passive design)

Window to wall ratio to be maintained

Balconies / roof deck required


Ground floor unit entry doors and concrete stoops required

3rd floor setback required

On-site parking required

Beyond optimizing envelope and systems, not many additional levers to pull!





PASSIVE BUILDING OVER PARKING

Explored multiple options, including structural frame + dropped ceilings


Final approach included insulating over standard concrete plank floor/ceiling assembly.

Introducing hi-load rigid insulation at critical bearing conditions

Simplified building geometry and double loaded corridor allowed for straightforward structural designs and simple foam pattern

Ultimately a simpler construction detail and execution than approaching thermal boundary at the underside of plank





CONTINUOUS AIR CONTROL LAYER


Self-adhered membrane

Flashing and balcony / roof sequencing with continuous insulation

Window buck assembly, flashed and fully air-sealed install








new assemblies, new priorities, and real performance targets

CONTINUOUS INSULATION


5" mineral wool board, furring / long screws

Roof deck area + balcony sequencing with continuous insulation

Detailing for continuity at transitions







passive building as a new concept

new assemblies, new priorities, and real performance targets



SOLAR SYSTEM SPECS


35.2 kW roof mounted ballasted array

44,000 kWh/yr

87 bifacial 405W panels, single slope (5 degree) orientation

Contributes to an equivalent EUI reduction of 4.46 kBTU/sf yr

PROJECTED ENERGY CONSUMPTION MIX





creative financing

4

market rate housing, no subsidies, equity and beyond

BUDGET CONSTRAINTS + TYPICAL VALUE MGMT APPROACH

Original GMP bid too high (appx. 9.0%) Note: Not exclusively passive building elements

Traditional value management process doesn't quite get us to target (still + 2.7% over budget)

In the meantime, how is sourcing debt in the capital markets...

252 Dunning - Original Budget (Pro Forma)		Per DU	Per GSF
Land Cost Soft Cost	\$600,000 \$1,410,000	\$18,750 \$44,063	\$19 \$44
Hard Cost (Budget)	\$8,480,000	\$265,000	\$264
Total Development Cost (Budget)	\$10,490,000	\$327,813	\$327

252 Dunning - Budget / Pricing	Cost	Per DU	Per GSF
Land Cost	\$600,000	\$18,750	\$19
Soft Cost	\$1,410,000	\$44,063	\$44
Hard Cost (GMP - Oct 2022)	\$9,420,000	\$294,375	\$294
Total Development Cost	\$11,430,000	\$357,188	\$356

+9.0%

252 Dunning - Budget / Pricing	Cost	Per DU	Per GSF
Land Cost Soft Cost	\$600,000 \$1,410,000	\$18,750 \$44,063	\$19 \$44
Value Management Process (Oct 2022 to July 2023)	-\$653,000		
Hard Cost (GMP - July 2023)	\$8,767,000	\$273,969	\$273
Total Development Cost	\$10,777,000	\$336,781	\$336

+2.7%

creative financing



market rate housing, no subsidies, equity and beyond

MARKET CONSTRAINTS + TRENDS

Historically low-interest rate environment


- Construction prices take time to reset
- US 10Y approaching 5% resulting in construction loans with rates around 6.5% to 7.25% +/-

Multifamily development yields (compressed) in Madison are at 5.5% to 6.25%

Investors have options

Negative leverage (loan constant > yield)

What do we do? We are over budget and cannot raise capital...



Source: Mortenson – Milwaukee Q2 2025

creative financing

4

market rate housing, no subsidies, equity and beyond

CREATIVE FINANCING STRATEGIES

Negative leverage = deleverage

Yields grow as leverage decreases

Soft costs (construction interest / financing fees) decrease as leverage decreases

Equity

1. the quality of being fair and just 2. ownership, value

Raise equity, or exchange equity in lieu of construction fees = use reduction, source reduction, stakeholder alignment

All equity – alignment and project savings

252 Dunning - Budget / Pricing	Cost	Per DU	Per GSF
Land Cost	\$600,000	\$18,750	\$19
Soft Cost	\$1,410,000	\$44,063	\$44
Hard Cost (GMP - Adjusted - July 2023)	\$8,767,000	\$273,969	\$273
Total Development Cost	\$10,777,000	\$336,781	\$336

+2.7%

All-Equity Financing Soft Cost Implications	Cost	Per DU	Per GSF
Soft Costs			
No Financing Fees / Construction Interest	-\$360,000	-\$11,250	-\$11
Additional Capital Placement Fees	\$100,000	\$3,125	\$3
Subtotal	-\$260,000	-\$8,125	-\$8
Adjusted Total Development Cost	\$10,517,000	\$328,656	\$328

+0.3% Close

All-Equity Financing Capital Placement	Cost	Per DU	Per GSF
Subcontractor (Equity In-Lieu of Fee)	-\$300,000	-\$9,375	-\$9
Adjusted Total Development Cost	\$10,217,000	\$319,281	\$318

WI	TI	HI	N
BU	D	GE	ΞT

Total Development Costs (Actual)	Cost	Per DU	Per GSF
Land Cost (Actual)	\$607,500	\$18,984	\$19
Soft Cost (Actual)	\$1,170,219	\$36,569	\$36
Hard Costs (Actual)	\$8,330,849	\$260,339	\$260
Total Development Cost (Actual)	\$10,108,567	\$315,893	\$315

SAVINGS

market rate housing, no subsidies, equity and beyond

COMPARING STRATEGIES + PATHWAYS


Market rate, side-by-side analysis with conventional approach

~8% premium when modeling Phius vs "Conventional"

Compared to conventional construction = appx. \$600,000 +/- premium or about \$40,000 of additional net operating income required to offset the increased capital expense

Energy savings is valued at appx. \$200,000 to \$250,000 at a 6% cap rate; capture additional value

Does not take into account value of other benefits.



IMPORTANT TO NOTE: THE TERM 'CONVENTIONAL' IS CONTEXTUAL HERE: ENTITLEMENTS AT THIS SITE WOULD HAVE REQUIRED SOME LEVEL OF 'GREEN' CERTIFICATION – THE 8% PREMIUM OVER CONVENTIONAL IS A NUANCED METRIC – FURTHERMORE, THE CONVENTIONAL PROJECTS USED IN THIS COMPARISON WERE NOT ADJUSTED FOR INFLATION OR COST ESCALATION

owning it

WHAT DID WE LEARN?

PROJECT AS BUILT

REPLICABLE?

REFINEMENTS FOR SCALABITY

Design complete, with passive building layered on as a last-minute requirement for approval

NO 💢

Performance goals' ability to influence design throughout the process is critical. Passive building focus from day one to allow design decisions to support performance goals

Design build MEP approach – other team members pick up the slack without EOR onboard early

MAYBE

?

Traditional design/bid/build approach OR must have complete trust in a team to be able to plan for and execute a design/build MEP design. Coordination is key.

Garage, balconies, stoops, exterior doors, setbacks – tricky to detail and ultimately costly

NC



Optimize design early on, push back on car-centric or antidensity requirements where appropriate.

Single source responsibility for high performance / passive building related scope and detailing

YES



Until passive building principles / training is required for code buildings, there is a need to fill those critical roles as they are integral to the success of construction.

All-equity financing

MAYBE



If the design is optimized and goals are established early on this could be a feasible solution, but entitlements and zoning requirements play a critical role in shaping a project, from both a design and ultimately cost perspective. Equity as financial approach and value alignment.



























