# Sustainable Specs Implementation of Passive Goals





# **AGENDA**

- Introduction
- What Belongs in Specifications?
- Performance vs. Prescriptive
- Construction Verification



- 1. Write Specifications
- 2. Review Specifications
- 3. Use Specifications

# **Phius 2024**

# PASSIVE BUILDING STANDARDS CERTIFICATION GUIDEBOOK












## **ENERGY CODE**






**DRAWINGS** 



**SPECIFICATIONS** 



# **Division 1 – General Requirements (Passive Building Spec)**

# **Division 3 – 5 – Structure (Structural Thermal Breaks)**

**Division 7 – 8 – Building Envelope (Air Barrier, Windows, Insulation)** 


**Division 9-12 – Interior | Finishes (Appliances, Fixtures, Blinds)** 

**Division 22 – Plumbing (DHW Equipment, Pipe Insulation)** 

**Division 23 – HVAC (HVAC Equipment, Ducts, Balanced Ventilation)** 

**Division 26 - Electrical (Distribution, Lighting)** 

### **SPECIFICATIONS**







# VERSION 1 (REV. 04) Indoor airPLUS CONSTRUCTION SPECIFICATIONS



February 2018 www.epa.gov/indoorairplus

Indoor Air Quality (IAQ)

# Indoor airPLUS Version 1 (Rev. 04) Verification Checklist



City:	State:	Zip:		
Radon Zone (1-3):				
s (Refer to full Indoor airPLUS Construction Specifications for details)	Must Correct	Builder Verified	Rater Verified	N/A
ecklist reflects only the additional Indoor airPLUS requirements and their in numbers that must be met after completing the ENERGY STAR GY STAR remains a prerequisite for Indoor airPLUS qualification.				
n 3 (or 3.1, 3.2) Program Requirements must be followed and the home shall ified in conjunction with Indoor airPLUS qualification.				
p pump installed in basements and crawlspaces. In EPA Radon Zone 1, check talled.				
plied: Slab-on-grade foundation Free-draining soils				
egate or sand (4 in.) with geotextile matting installed below slabs AND radon sed in EPA Radon Zone 1.				
plied: ☐ Slab-on-grade foundation ☐ Free-draining soils ☐ Dry cl	imate			
rawlspaces insulated, sealed and conditioned.				
plied:   100-year flood zone	imate I pier founda	ation with n	o walls	
om water splash damage if no gutters.				
plied: ☐ Rainwater harvesting system ☐ Dry climates				
in exterior walls insulated with pipe wrap.				
plied: Dry climate AND climate zone 1-3 Air barrier insulation in wal	cavity			
flooring in kitchens, baths, entry, laundry, and utility rooms.				
ant features installed in Radon Zone 1 homes in accordance with Construction 2.1.			_	
plied: Perimeter pipe loop in lieu of full aggregate (dry climate)	actured hom	e with raise	d pier found	dation
of rodent/bird screens installed at all openings that cannot be fully sealed. I for clothes dryer vents.)	0		0	
flected to keep relative humidity < 60% in "Warm-Humid" climates.				
plied: Climate zones 4-8, 3B, 3C and portions of 3A and 2B				
protected from construction debris AND no building cavities used as air turns.				
ng equipment or ductwork installed in garage.				
s vented to the outdoors or plumbed to a drain according to manufacturer's			0	
d-air HVAC system(s) have minimum MERV 8 filter AND no ozone generators sporary filter installed to protect unit from construction dust.				
ndards met for fuel-burning and space-heating appliances.				
ance type:				
stalled in each sleeping zone (e.g., common hallway) according to NFPA 720.				
uildings: Smoking restrictions implemented AND ETS transfer pathways				
ages: Door closer installed on all connecting doors.				
ages: In homes with exhaust-only whole-house ventilation EITHER aust fan installed in garage OR ast conducted to verify the effectiveness of the garage-to-house air barrier.	0		0	0
The state of the state of the Boards to 1/000c on political				

Indoor sirPHIS Verd	ion 1 (Rev. 04) Co.	netruction Specifics	tions (February 2018) 3

vood products certified low-emission. See spec.				
and finishes certified low-emission. See spec.				
adhesives, and carpet cushion certified low	-emission. See spec.			
nd ductwork verified to be dry and clean A	ND new filter installed.			
ed before occupancy.				
nuals, Indoor airPLUS label, and certificate	provided for owner/occupant.			
Date:	Builder Company:	Date	a:	_
Date:	bullder Signature:	 Date	*:	

#### mpleting the Indoor airPLUS Verification Checklist:

homes verified to comply with these specifications can earn the Indoor airPLUS label. See Indoor airPLUS or full descriptions of the requirements, terms, exceptions, abbreviations, references and climate map used in this implete until this checklist is completed in full and signed.

es and exceptions will always be utilized unless otherwise noted in the Indoor airPLUS Construction Specifications.

5 modifies or excludes certain ENERGY STAR exceptions or alternate pathways.

k "N/A" for specifications that do not apply for specific conditions (e.g., climate) according to the exceptions US Construction Specifications. Check either "Builder Verified" or "Rater Verified" for all other items to indicate s may be verified visually on site during construction, by reviewing photographs taken during construction, by through equivalent methods as appropriate.

a verification, or a responsible party from the Rater's company, must sign the completed verification checklist. e checklist if any items in the "Builder Verified" column are checked, and by so doing accepts full responsibility for set Indoor airPLUS requirements.

ing documentation, all required ENERGY STAR Certified Homes documentation, and the Indoor airPLUS home for a minimum of 2 years from final verification. The Rater shall coordinate with the Provider and/or airPLUS label and certificate for each qualified home.

Sampling Provider are permitted to use a RESNET-approved sampling protocol for Indoor airPLUS homes located piling protocol approved by the California Energy Commission for homes located in California, to verify any item For example, if the approved sampling protocol requires rating one in seven homes, then the checklist will be that was rated. Only Raters are permitted to use sampling. All items verified by the builder shall be verified for within a multifamily building. For example, if a Rater verifies 10 items on the indoor airPLUS Checklist and the checklist items, then an approved sampling protocol is permitted to be used only on the 10 Rater-verified items.

ovide the Rater with a single signed copy of the checklist for an entire building or group of units with builderiltion that all units within the building or group utilize: 1) the same HVAC system type (i.e. ductless mini-split,
ame combustion appliances and combustion pollutant controls; and 3) the same low-emission materials
products (within their respective categories) verified in Section 6 of the Indoor airPLUS Construction
builder-verified items, the Rater may also utilize one checklist per group of units if the above criteria are met.
he following conditions will require a separate and unique checklist to be completed and signed by the Rater and

HVAC system type (i.e., ductless mini-split, forced air, hydronic);

combustion appliance types (e.g., masonry heater, pellet stove, wood-burning fireplace) stove, factory-built, etc.) controls; or Any units/groups with low-emission materials or finishes addressed in Section 6 that are compliant lications/standards within their product category.

Raters may use a single checklist for units utilizing low-emission materials certified to different labels or t documentation of the certifications for those materials are retained by the builder and available for inspection

the Indoor airPLUS
ov/indoorairplus.



All Indoor airPLUS qualified homes meet strict
guidelines for energy efficiency set by ENERGY STAR,
the nationally-recognized symbol for energy efficiency.

Indoor airPLUS Version 1 (Rev. 04) Construction Specifications (February 2018) 4

	als	6.1	All composite wood products certified low-emission. See spec.					
	6.1 All composite wood products certified low-emission. See spec.  6.2 Interior paints and finishes certified low-emission. See spec.  6.3 Carpet, carpet adhesives, and carpet cushion certified low-emission. See spec.							
	6.3 Carpet, carpet adhesives, and carpet cushion certified low-emission. See spec.							
	7.1 HVAC system and ductwork verified to be dry and clean AND new filter installed.							
	7.2 Home ventilated before occupancy.							
	_	7.3	Equipment manuals, Indoor airPLUS label, and certificate provided for owner/occupant.					
Rater Company: Builder Company:  Rater Employee: Builder Employee:								
K	ater Em	pioyee		Builder Employee:				
Ra	ater Sigi	nature:	Date:	Builder Signature:		Date	e:	

# **Guidance for Completing the Indoor airPLUS Verification Checklist:**

- Only ENERGY STAR certified homes verified to comply with these specifications can earn the Indoor airPLUS label. See Indoor airPLUS
   Construction Specifications for full descriptions of the requirements, terms, exceptions, abbreviations, references and climate map used in this checklist. Verification is not complete until this checklist is completed in full and signed.
  - Note: ENERGY STAR footnotes and exceptions will always be utilized unless otherwise noted in the Indoor airPLUS Construction Specifications. In some cases, Indoor airPLUS modifies or excludes certain ENERGY STAR exceptions or alternate pathways.
- 2. Check one box per line. Check "N/A" for specifications that do not apply for specific conditions (e.g., climate) according to the exceptions described in the Indoor airPLUS Construction Specifications. Check either "Builder Verified" or "Rater Verified" for all other items to indicate who verified each item. Items may be verified visually on site during construction, by reviewing photographs taken during construction, by checking documentation, or through equivalent methods as appropriate.

#### 6.2 Interior Paints and Finishes

#### **Indoor airPLUS Requirements:**

- At least 90 percent of the interior surface area covered by siteapplied paints and coatings shall use low-VOC or no-VOC products certified by one of the following third-party standards or certifications:
  - GREENGUARD or GREENGUARD GOLD Certification for Paints and Coatings, OR
  - Scientific Certification Systems (SCS) Standard EC-10.3-2014, Indoor Advantage Gold, OR
  - A third-party low-emitting product list based on CA Section 01350 (CDPH Standard Method V1.2-2017), OR
  - o Green Seal Standard GS-11, OR
  - Green Wise and Green Wise Gold products, OR
  - Master Painters Institute (MPI) Green Performance Standards X-Green, GPS-1 or GPS-2.

#### 6.4 Adhesives and Sealants

**Advisory**: While not currently required by Indoor airPLUS, EPA recommends that at least 90 percent of site-applied interior adhesives and sealants be low-VOC or no-VOC products certified by one of the following third-party standards or certifications:

- A third-party low-emitting product list based on CA Section 01350 (CDPH Standard Method V1.2-2010), OR
- Green Seal GS-36, OR
- GREENGUARD or GREENGUARD GOLD certification for adhesives and sealants.
- Hardwood plywood: Use only products certified compliant with:
  - Formaldehyde emissions requirements of ANSI/HPVA HP-1-2016; OR
  - California Air Resources Board (CARB) Airborne Toxics
     Control Measure (ATCM) Phase II to Reduce
     Formaldehyde Emissions from Composite Wood Products;
     OR
  - EPA Toxic Substances Control Act (TSCA) Title VI certified.



# Indoor AirPlus Verification Requirements VERSION 2























y: Microwave-range hood exhaust airflow not measured; meets additional		I .	
v: Downdraft exhaust fan installed with electric cooktop and ≥ 300 CFM.			
aust is present in the kitchen, exhaust grille meets cooking equipment separation			
MERV 3 or washable filter.		П	ш
n exhaust rated ≤ 1 sone at airflow ≥ 25 CFM.			
d kitchen exhaust rated ≤ 2 sone at airflow ≥ 100 CFM.			
, HRV, in-line fan Remote-mounted fan		_	-
entilation air provided directly from outdoors and inlets meet separation distances.	П		П
entilation and exhaust measured to meet or exceed ASHRAE 62.1-2019.			-
tion, common space ventilation outdoor air passes through a filter rated:			
igher (CERTIFIED)			_
er is accessible for maintenance.			
ystems exhaust outdoors and ≥ 10 ft. from ventilation air inlets.			
yers exhaust outdoors.			
, ducted HAC systems include clean filters rated:			
gher (CERTIFIED)			
alling units with portable air cleaners:	"		"
(IFIED)		ı	
ers are accessible for cleaning and/or replacement.			
is are gasketed and/or sealed.			
mechanically supplied outdoor air pass through a filter.	-		-
ners do not generate ozone exceeding concentration limits of 0.005 ppm.			
or devices intentionally using ozone not installed.			-
e following filtration methods provided for dwelling units with no ducted HAC			
her Portable air cleaners Transfer fan w/ MERV 13 or higher			
air cleaning devices are installed, ozone is not intentionally used.			
UVGI or other electronic air cleaners (e.g., plasma generators, PCOs, etc.) must not	_	_	_
ncentration limits of 0.005ppm.			
mental and a coopping			_
	Must		
	Must	Verified	N/A
	Correct		N/A
por AirPlus requirements shown in italics are satisfied by meeting related ENERGY STA	Correct		N/A
tions are permitted unless otherwise specified.	Correct		N/A
	Correct AR requirem	nents, and	
tions are permitted unless otherwise specified.	Correct		N/A
tions are permitted unless otherwise specified. turally drafted appliances meet max depressurization and exhaust location	Correct AR requirem	nents, and	
tons are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.	Correct AR requirem	nents, and	
tons are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  nically drafted or direct-vented.	Correct AR requirem	nents, and	0
tions are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  inically drafted or direct-vented.  urning fireplaces have tempered glass front or gasketed door.	AR requirem	ents, and	0
tons are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  uning drafted or direct-vented.  uning fireplaces have tempered glass front or gasketed door.  bustion appliances other than cooktops/ranges/ovens.	Correct AR requirem	ents, and	0
tions are permitted unless otherwise specified.  sturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  nically drafted or direct-vented.  urning fireplaces have tempered glass front or gasketed door.  blustion appliances other than cooktops/ranges/ovens.  and flues pass professional Level II inspection per NFPA 211.	AR requirem	ents, and	0
tions are permitted unless otherwise specified.  strongly drafted appliances meet max depressurization and exhaust location strong furnaces, boilers, water heaters mechanically drafted or direct-vented.  inicially drafted or direct-vented.  unting fireplaces have tempered glass front or gasketed door, bustion appliances other than cooktops/ranges/ovens.  and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):	Correct AR requirem	ents, and	0
tons are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Iturally drafted or direct-vented.  Iturally drafted or direct-vented.  Iturally drafted or direct-vented.  Iturally drafted door.  Iturally drafted or direct-vented.  Iturally drafted door.  Iturally drafted or direct-vented.  Iturally drafted or	Correct AR requirem	ents, and	0
tions are permitted unless otherwise specified.  storally drafted appliances meet max depressurization and exhaust location storal furnaces, boilers, water heaters mechanically drafted or direct-vented.  uning fireplaces have tempered glass front or gasketed door.  bustion appliances other than cooktops/ranges/ovens.  and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):   nry fireplaces sealed to prevent use or are retrofitted  ood burning fireplaces have dedicated outdoor air & meet UL 127	Correct AR requirem	ents, and	0
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Ituring fireplaces have tempered glass front or gasketed door,  Ibustion appliances other than cooktops/ranges/ovens.  Ituring fireplaces have tempered glass front or gasketed door,  Ibustion appliances other than cooktops/ranges/ovens.  Ituring fireplaces sealed to prevent use or are retrofitted  Ituring fireplaces have dedicated outdoor air & meet UL 127  Ipplace inserts meet UL 1482 and the EPA's New Source Performance Standards	Correct AR requirem	ents, and	0
tons are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Iturally drafted door.  Iturally	Correct AR requirem	ents, and	0
tions are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or a set of the set of	Correct AR requirem	nents, and	
tions are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or a set of the set of	Correct AR requirem	ents, and	0
tions are permitted unless otherwise specified turally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented. inicially drafted or direct-vented.  uning fireplaces have tempered glass front or gasketed door, tustion appliances other than cooktops/ranges/ovens. s and flues pass professional Level II inspection per NFPA 211, appliances meet the following requirements (check where applicable): my fireplaces sealed to prevent use or are retrofitted ood burning fireplaces have dedicated outdoor air & meet UL 127 pplace inserts meet UL 1482 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's New Source Performance Standards alled according to 2021 IBC Section 915 or 2021 IBC Section R315. protected from dust, paint, and contaminants during construction.	Correct AR requirem	nents, and	0 0 0
trons are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location stron furnaces, boilers, water heaters mechanically drafted or direct-vented.  Iturally appliances other than cooktops/ranges/ovens.  Iturally appliances other than cooktops/ranges/ovens.  Iturally appliances meet the following requirements (check where applicable):  Iturally drafted or drafted or are retrofitted or drafted or	Correct AR requirem	nents, and	
tions are permitted unless otherwise specified.  storally drafted appliances meet max depressurization and exhaust location storal furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or services and fluss pass professional Level II inspection per NFPA 211.  In appliances meet the following requirements (check where applicable): Initially drafted or prevent use or are retrofitted one durning fireplaces have dedicated outdoor air & meet UL 127 splace inserts meet UL 1482 and the EPA's New Source Performance Standards seet ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards select ASTM E1509 and	Correct AR requirem	nents, and	0 0 0
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Ituring fireplaces have tempered glass front or gasketed door, bustion appliances other than cooktops/ranges/ovens.  It and flues pass professional Level II inspection per NFPA 211, appliances meet the following requirements (check where applicable): my fireplaces sealed to prevent use or are retrofitted ood burning fireplaces have dedicated outdoor air & meet UL 127 pplace inserts meet UL 1482 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's New Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards neet ASTM E1509 and the EPA's new Source Performance Standards new Source Performance Stan	Correct AR requirem	eents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented. Incitally drafted or application appliances have tempered glass front or gasketed door. Incitally drafted or prevent use or are retrofitted or door during fireplaces have dedicated outdoor air & meet UL 127 pplace inserts meet UL 1482 and the EPA's New Source Performance Standards salted according to 2021 IBC Section 915 or 2021 IBC Section R315. protected from dust, paint, and contaminants during construction. In with the EPA's brochure or resource guide on secondhand smoke, uldings, smoking/vaping prohibition is posted in common areas and communicated in allidings, where provided, designated outdoor smoking/vaping areas located a	Correct AR requirem	nents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  Is and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  Iny fireplaces headed to prevent use or are retrofitted  obed burning fireplaces have dedicated outdoor air & meet UL 127  splace inserts meet UL 1482 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  alled according to 2021 IBC Section 915 or 2021 IBC Section 8315.  protected from dust, paint, and contaminants during construction.  It with the EPA's brochure or resource guide on secondhand smoke,  juidings, smoking/vaping prohibition is posted in common areas and communicated in  alidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows.	Correct AR requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Iturally drafted or direct-vented.  Itura	Correct AR requirem	eents, and	
tions are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented. Unling fireplaces have tempered glass front or gasketed door. Industrial programmes of their than cooktops/ranges/ovens.  se and fluse pass professional Level II inspection per NFPA 211. appliances meet the following requirements (check where applicable): my fireplaces have dedicated outdoor air & meet UL 127 appliances meet UL 1482 and the EPA's New Source Performance Standards obed burning fireplaces have dedicated outdoor air & meet UL 127 appliance inserts meet UL 1482 and the EPA's New Source Performance Standards seet ASTM E1509 and the EPA's New Source Performance Standards alled according to 2021 IBC Section 915 or 2021 IBC Section R315. protected from dust, paint, and contaminants during construction, did with the EPA's brochure or resource guide on secondhand smoke. Indings, smoking/vaping prohibition is posted in common areas and communicated in didings, where provided, designated outdoor smoking/vaping areas located a from entries, outdoor air intakes, and operable windows. basements not vented, and perimeter walls sealed.  g in accordance with ANSVIESSNET/ICC Std. 380 is met:	Correct AR requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Ituring fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  Ituring fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  Ituring fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  Ituring fireplaces have tempered glass front or gasketed door,  bustion appliances meet the following requirements (check where applicable):  ny fireplaces sealed to prevent use or are retrofitted  bustion door burning fireplaces have dedicated outdoor air & meet UL 127  paper grade inserts meet UL 1482 and the EPA's New Source Performance Standards  alled according to 2021 IBC Section 915 or 2021 IBC Section 9315.  protected from dust, paint, and contaminants during construction.  It with the EPA's brochure or resource guide on secondhand smoke,  uidings, smoking/vaping prohibition is posted in common areas and communicated in  alidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows.  basements not vented, and perimeter walls sealed.  It is a coordance with ANSI/RESNET/ICC Std. 380 is met:  trached dwelling units > 1,000 ft?, ≤ 5 ACH50	Correct	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location stion furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented.  Iturally drafted or	Correct AR requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have decided for great glass from the properties of the great glass from the great glass	Correct	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have tempered glass front or gasketed door. Ituring fireplaces have decided for great glass from the properties of the great glass from the great glass	Correct	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  It and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  In priceplaces sealed to prevent use or are retrofitted  dood burning fireplaces have dedicated outdoor air & meet UL 127  uppliance inserts meet UL 1482 and the EPA's New Source Performance Standards  lated according to 2021 IBC Section 913 or 2021 IBC Section 913 is.  protected from dust, paint, and contaminants during construction.  It with the EPA's brochure or resource guide on secondhand smoke,  uidings, smoking/vaping prohibition is posted in common areas and communicated in  allidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows,  basements not vented, and perimeter walls sealed.  In our coordance with ANSI/RESNETI/CC Std. 380 is met:  trached dwelling units > 1,000 ft?, ≤ 3 ACH50  other units ≤ 0.30 CFM50/sf encl.  ed dwelling units > 1,000 ft?, ≤ 3 ACH50  runits ≤ 0.25 CFM50/sf encl.	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  Is and flues pass professional Level II inspection per NFPA 211.  Appliances meet the following requirements (check where applicable):  Inny fireplaces sealed to prevent use or are retrofitted  ood burning fireplaces have dedicated outdoor air & meet UL 127  populace inserts meet UL 1482 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet ASTM E1509 and the EPA's new Source Performance Standards  seet AST	Correct	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Unting fireplaces have tempered glass front or gasketed door.  Ibustion appliances other than cooktops/ranges/ovens.  Is and flues pass professional Level II inspection per NFPA 211.  Imaginances meet the following requirements (check where applicable):  Inny fireplaces sealed to prevent use or are retrofitted  ood burning fireplaces have dedicated outdoor air & meet UL 127  Ispace inserts meet UL 1482 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  seet A	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented.  Initially drafted or direct-vented.  Iturally drafted or direct-vented.  Itural	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location ston furnaces, boilers, water heaters mechanically drafted or direct-vented. Initially drafted or direct-vented. Unling fireplaces have tempered glass front or gasketed door. Industrial programmes of their than cooktops/ranges/ovens.  Is and flues pass professional Level II inspection per NFPA 211.  Appliances meet the following requirements (check where applicable): my fireplaces have tempered glass front or gasketed door. In programmes to the cook where applicable to prevent use or are retrofitted ood burning fireplaces have dedicated outdoor air & meet UL 127 pplace inserts meet UL 1482 and the EPA's New Source Performance Standards seet ASTM E1509 and the EPA's New Source Performance Standards seet ASTM E1509 and the EPA's New Source Performance Standards alled according to 2021 IBC Section 915 or 2021 IBC Section 9315. protected from dust, paint, and contaminants during construction, did with the EPA's brochure or resource guide on secondanad smoke, and did not seen the second programme of	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door.  Bustion appliances other than cooktops/ranges/ovens.  Is and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  Iny fireplaces sealed to prevent use or are retrofitted  obed burning fireplaces have dedicated outdoor air & meet UL 127  appliances meet the following requirements (check where applicable):  Iny fireplaces sealed to prevent use or are retrofitted  obed burning fireplaces have dedicated outdoor air & meet UL 127  appliances meet UL 1482 and the EPA's New Source Performance Standards  seet ASTM E1509 and the EPA's New Source Performance Standards  alled according to 2021 IBC Section 915 or 2021 IBC Section 9315.  protected from dust, paint, and contaminants during construction.  If with the EPA's brochure or resource guide on secondhand smoke,  uiddings, where provided, designated outdoor smoking/vaping areas located in  alidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows.  basements not vented, and perimeter walls sealed.  If an accordance with ANSI/RESNET/ICC Std. 380 is met:  tached dwelling units > 1,000 ft², ≤ 5 ACH50  Tunits ≤ 0.30 CFM50/sf encl.  ed dwelling units > 1,000 ft², ≤ 5 ACH50  Tunits ≤ 0.25 CFM50/sf encl.  ed dwelling units > 1,000 ft², ≤ 3 ACH50  Tunits ≤ 0.25 CFM50/sf encl.  ed welling and townhouses with attached private garages:  onducted to verify effectiveness of garage-to-house air barrier; OR  tatached dwelling under a description of the sealer of the seale	Correct R requirem	ents, and	
toral permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  uming fireplaces have tempered glass front or gasketed door.  bustion appliances other than cooktops/ranges/ovens.  sand fluse pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  ny fireplaces sealed to prevent use or are retrofitted  ood burning fireplaces have dedicated outdoor air & meet UL 127  place inserts meet UL 1482 and the EPA's New Source Performance Standards  self ASTM E1509 and the EPA's New Source Performance Standards  alled according to 2021 IBC Section 915 or 2021 IRC Section R315.  protected from dust, paint, and contaminants during construction.  d with the EPA's brochure or resource guide on secondhand smoke.  Indigns, smoking/vaping prohibition is posted in common areas and communicated in  alidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows.  basements not vented, and perimeter walls sealed.  The provided of the provided of the perimeter walls sealed.  The	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  turally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door.  Bustion appliances other than cooktops/ranges/ovens.  Is and fluse pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  The properties are selected to prevent use or are retrofitted ood burning fireplaces have dedicated outdoor air & meet UL 127  place inserts meet UL 1482 and the EPA's New Source Performance Standards select ASTM E1509 and the EPA's New Source Performance Standards alled according to 2021 IBC Section 915 or 2021 IRC Section R315.  protected from dust, paint, and contaminants during construction.  In with the EPA's brochure or resource guide on secondhand smoke.  Indings, smoking/vaping prohibition is posted in common areas and communicated in alidings, where provided, designated outdoor smoking/vaping areas located a from entries, outdoor air intakes, and operable windows.  Basements not vented, and perimeter walls sealed.  In an accordance with ANSIMESNET/ICC Std. 380 is met:  Tatached dwelling units > 1,000 ft°, ≤ 5 ACH50  other units ≤ 0.30 CFM50/sf encl.  end dwelling units > 1,000 ft°, ≤ 3 ACH50  runts ≤ 0.25 CFM50/sf encl.  end grages and occupiable spaces are air-sealed and doors are gasketed or ally dwellings and townhouses with attached private garages: conducted to verify effectiveness of garage-to-house air barrier; OR tabled in garage and verifier-measured airflow ≥ 100 CFM  wildings, where an exhaust systems is installed in a shared parking garage, system woods.	Correct R requirem	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Inicially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door,  bustion appliances other than cooktops/ranges/ovens.  It and flues pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  In priceplaces sealed to prevent use or are retrofitted  dood burning fireplaces have dedicated outdoor air & meet UL 127  uppliance inserts meet UL 1482 and the EPA's New Source Performance Standards  lated according to 2021 IBC Section 913 or 2021 IBC Section 913 is.  protected from dust, paint, and contaminants during construction.  It with the EPA's brochure or resource guide on secondhand smoke,  uidings, smoking/vaping prohibition is posted in common areas and communicated in  allidings, where provided, designated outdoor smoking/vaping areas located a  from entries, outdoor air intakes, and operable windows,  basements not vented, and perimeter walls sealed.  In our coordance with ANSI/RESNETI/CC Std. 380 is met:  trached dwelling units > 1,000 ft?, ≤ 3 ACH50  other units ≤ 0.30 CFM50/sf encl.  ed dwelling units > 1,000 ft?, ≤ 3 ACH50  runits ≤ 0.25 CFM50/sf encl.	Correct	ents, and	
tions are permitted unless otherwise specified.  Iturally drafted appliances meet max depressurization and exhaust location  stion furnaces, boilers, water heaters mechanically drafted or direct-vented.  Initially drafted or direct-vented.  Uning fireplaces have tempered glass front or gasketed door.  Ibustion appliances other than cooktops/ranges/ovens.  Is and fluse pass professional Level II inspection per NFPA 211.  appliances meet the following requirements (check where applicable):  Iny fireplaces have tempered glass front or gasketed door.  Bood burning fireplaces have dedicated outdoor all is meet UL 127  papace inserts meet UL 1482 and the EPA's New Source Performance Standards seet ASTM £1509 and the EPA's New Source Performance Standards seet ASTM £1509 and the EPA's New Source Performance Standards seled according to 2021 IBC Section 915 or 2021 IBC Section 8315.  protected from dust, paint, and contaminants during construction.  If with the EPA's brochure or resource guide on secondhand smoke.  Indings, smoking/vaping prohibition is posted in common areas and communicated in alidings, where provided, designated outdoor smoking/vaping areas located a from entries, outdoor air intakes, and operable windows.  Basements not vented, and perimeter walls sealed.  In an accordance with ANSI/RESNET/ICC Std. 380 is met:  Itached dwelling units > 1,000 ft°, ≤ 3 ACH50  Tunits ≤ 0.30 CFM50/sf encl.  end grapes and occupiable spaces are air-sealed and doors are gasketed or only dwellings and townhouses with attached private garages:  Tonducted to verify effectiveness of garage-to-house air barrier; OR tabled in garage and Verifier-measured airflow ≥ 100 CFM  Wildings, where an exhaust system is installed in a shared parking garage, system NO2 sensors, meeting minmum continuous ventilation rates.	Correct R requirem	ents, and	

led)			Must Correct	Verified	N/A
ing Products guide to h	elp identify compliant products,				
meet VOC emission li	mits in CDPH Standard Method V1.2	-2017.			
meet VOC emission lim	its in CDPH Standard Method V1.2-2	017.			
t VOC emission limits i	n CDPH Standard Method V1.2-2017				
derlayment meet VOC	emission limits in CDPH Standard Me	ethod V1.2-			
int compound meet VC	C emission limits in CDPH Standard	Method V1.2-			
neet VOC emission limi	ts in CDPH Standard Method V1.2-20	017.			
			Must Correct	Verified	N/A
systems ttors				r Responsib	,
recommendations and	filter change schedule provided.		Builde	r Responsib	ility
gible print, except for	"Initials" which can be signed/initia	aled either manu	ially or dig	itally in this	3
	Home Certification Organization				
	First Inspection Date			Initials	

le Paperwork Reduction Act, 44 U.S.C. 3501 et seq. (OMB Control No. 2060-New). Responses to this collection of information are may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid ap burden for this collection of information is estimated to .5 hours per response. Send comments on the Agency's need for this s and any suggested methods for minimizing respondent Burden to the Regulatory Support Division Director, U.S. Environmental Vashington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed form to this address.

Final Inspection Date

July 2024 www.epa.gov/indoorairplus

Indoor Air Quality (IAQ)

ersion 2 (July 2024) Updated 9/12/24

Initials

Section	6 – Building Materials ( <u>newly installed</u> )	Must Correct	Verified	N/A
Downloa	ad the Indoor AirPlus Compliant Building Products guide to help identify compliant products,			
6.1	6.1.1 Paints, finishes, and coatings meet VOC emission limits in CDPH Standard Method V1.2-2017.			
6.2	6.2.1 Carpet and carpet cushions meet VOC emission limits in CDPH Standard Method V1.2-2017.			
6.3	6.3.1 Adhesives and sealants meet VOC emission limits in CDPH Standard Method V1.2-2017.			
6.4	6.4.1 Hard surface flooring and underlayment meet VOC emission limits in CDPH Standard Method V1.2-2017.			
6.5	6.5.1 Interior gypsum board and joint compound meet VOC emission limits in CDPH Standard Method V1.2-2017.			
6.6	6.6.1 GOLD: Insulation materials meet VOC emission limits in CDPH Standard Method V1.2-2017.			
Section	7 – Occupant Education	Must Correct	Verified	N/A
	<ul> <li>7.1.1 Instruction manuals provided for the following <u>newly installed</u> appliances and systems.</li> <li>■ HAC systems and accessories</li> <li>■ Local and dwelling-unit ventilation systems</li> </ul>			
7.1	<ul> <li>Kitchen and bath exhaust systems</li> <li>Air cleaners</li> <li>Dehumidifiers</li> <li>Moisture and/or IAQ monitors</li> <li>Combustion appliances</li> <li>Sump pumps</li> <li>Radon systems</li> </ul>	Builder	Responsib	ility

**Home Certification Organization** 

Verifier Organization

# STANDARD METHOD FOR THE TESTING AND EVALUATION OF VOLATILE ORGANIC CHEMICAL EMISSIONS FROM INDOOR SOURCES USING ENVIRONMENTAL CHAMBERS

#### Version 1.2

(Emission testing method for California Specification 01350.

Supersedes the previous version of

STANDARD PRACTICE FOR THE TESTING OF VOLATILE ORGANIC EMISSIONS FROM VARIOUS SOURCES

USING SMALL-SCALE ENVIRONMENTAL CHAMBERS)

#### PREPARED BY:

Indoor Air Quality Section
Environmental Health Laboratory Branch
Division of Environmental and Occupational Disease Control
California Department of Public Health

JANUARY 2017



California Department of Public Health Dr. KAREN SMITH, Director

California Health and Human Services Agency DIANA DOOLEY, Secretary



State of California EDMUND G. BROWN JR., Governor



# Indoor AirPlus: How to Find Compliant Building Materials

July 2024



Office of Air and Radiation EPA 402/K-24/002 | July 2024

# WHAT BELONGS IN SPECIFICATIONS?

Indoor Air Nothing
How to Find Compliant Buil 2.9 Minclude as Appendix July 2024



#### CRI Green Label Plus, by Carpet and Rug Institute.

Find CRI Green Label Plus products at:

Rug Institute's Green Label Plus products.




#### Benchmark VOC Green Certification.

Find Benchmark VOC Green Certified products at:



#### Clean Air GOLD, by Intertek.

Find Clean Air GOLD certified products at:



#### ClearChem, by Berkeley Analytical.

Find ClearChem certified products at:



#### FloorScore, by Scientific Certification Systems.

Find FloorScore certified products at:





#### Indoor Advantage Gold, by Scientific Certification Systems.

Find Indoor Advantage Gold certified products at:




#### Indoor Air Comfort USA, By Eurofins.

Find Indoor Air Comfort USA certified products at: www.eurofins.com/Indoor-Air-Comfort-USA.

EPA 402/K-24/002 | July 2024







## **ENCLOSURES**

**INSULATION** 

## **INTERIORS**

## **MEP**


**APPLIANCES** 

















## **ENCLOSURES**




## **INTERIORS**



## **MEP**







# **PERFORMANCE**

# VS.

# **PRESCRIPTIVE**



U-Frame Manufacturer

U-Glass Product

Solar Heat Gain Coefficient Glass Makeup

Condensation Resistance Factow E Coating

## **PERFORMANCE**

# VS.

## **PRESCRIPTIVE**

- B. Basis-of-Design Manufacturer: Intus Windows.
  - Series: Supera Fixed & Supera CW, Flangeless.
  - Operation: Casement, Fixed.
  - Finish: To be selected by Architect.
  - Accessories
    - Brick Extension
    - b. Strap anchors, structural aluminum
    - c. Screen with operable windows
    - d. WOCD (window operation control devise)
  - Performance, Assembly, Supera Fixed.
    - U-value: 0.14.
    - b. Air Infiltration Rate: <0.1 cfm/sq ft.
    - c. Water Penetration: 9.19 psf.
    - d. Acoustic Performance: STC of 31 and OITC of 25.
    - e. PSI-opaque: TBD

#### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Basis-of-Design Manufacturer: Okonoplat Pava, finish as selected by Architect from manufacturer's full range including 'non-standard colors.'
  - Vision Glass: Viracon VE1-2M or equal.
- B. Available Manufacturer: Intus Supera 74

## **ENCLOSURES**




## **INTERIORS**



## **MEP**










LIGHTING

**BLINDS** 

- 1. Prescriptive as much as possible
- 2. Performance per WUFI Passive
- 3. It depends...

AIR BARRIERS









# phius Quality Control Field Checklist, v24.1.1

Project #	Project Name City	S	tate
	1 - Building Envelope		
1.0	Site Photos Scan QR Code to view examples of site photos, Don'ts and Do's:		
1.0.1	Insulated Assemblies:	Rater/Verifier Confirmed	N/A
	Take photos of all insulated assemblies, to include measured insulation thickness and material type. Include	ide photos that show o	ontext and
1.0.1.1	clearly show depth, quality, and area(s) insulated. Save photos into project folder: 4. PHIUS+ On-Site Verifi Footings	cation.	
1.0.1.2	Foundation Wall		
1.0.1.3	Slab (including perimeter)		
1.0.1.4	Framed Floor		
1.0.1.5	Above-Grade Wall (interior and exterior insulation as applicable)		
1.0.1.6	Ceiling/Attic (interior and exterior insulation as applicable)		
Notes:			
1.0.2	Windows & Doors:	Rater/Verifier Confirmed	N/A
	Take a photo of the NFRC label, if available. Include photos that show window installed, U-value, and SHG PHIUS+ On-Site Verification. If NFRC data is not available, see requirements within the Key Documents tall Rater/Verifier Workbook.		
1.0.2.1	NFRC label on Fixed Window(s)		
1.0.2.2	NFRC label on Operable Window(s)		
1.0.2.3	NFRC label on Skylight (s)		
1.0.2.4	NFRC label on Glazed Door(s)		
1.0.2.5	Photo of Opaque Door(s)		
1.0.2.6	Photo of exterior access doors (roof access, attic access, etc.)		
Notes:			
1.0.3	Infrared Photos:	Rater/Verifier Confirmed	N/A
	Perform a thorough IR scan of the building thermal envelope. Provide representative photos, including, be corners, window frames, suspended floors, overhangs, and roofs. Include photos that indicate any therm folder: 4, PHIUS- On-Site Verification.		
1.0.3.1	Above-Grade Walls		
1.0.3.2	Ceiling/Attic		
1.0.3.3	Window Installed		
1.0.3.4	Framed Floor over unconditioned spaces		
Notes			
1.0.4	General Exterior:	Rater/Verifier Confirmed	N/A
	Take exterior photos of each elevation and significant architectural features including balconies, overhang of the areas surrounding, and adjacent to the building. Include photos that show any nearby structures, r can cause shading on the building. Save photos into project folder: 4. PHIUS+ On-Site Verification.		
1.0.4.1	Radon system piping (where applicable)		
1.0.4.2	Photos of Each Exterior Elevation		
1.0.4.3	Overhangs & Shading		
1.0.4.4	Surrounding Site and adjacent obstructions		
Notes:			



1.1	Field Verification  Rater/Verifier is responsible for verifying the tasks below ha
1.1.1	Architectural Features, Insulation, and Thermal Bridging
1.1.1.1	<b>Drawings Check:</b> Describe any significant variations in construction from th construction drawings and specifications (insulation, window sizes, window performance, fixed shading etc.).
Notes:	
1.1.1.2	Framing Inspection: Framing matches architectural plans (depth & spacing, 2x6 16" O.C.). If not, please describe in notes section below.
Notes:	
1.1.1.3	<b>Operable Shading:</b> If operable shading has been installed, describe operable shading.
Notes:	
1.1.1.4	<b>Insulation R-Value:</b> All insulation R-values match those listed on architectural plans. If not, please describe in notes section below.
Notes:	
1.1.1.5	<b>Insulation Quality Check:</b> All insulated assemblies have achieved a RESNET I cavity insulation level, or alternatively Grade II with continuous insulation.
Notes:	
1.1.1.6	Fastener Quality Check: In the box below, describe the material of fastener to install exterior insulation (aluminum, mild steel, stainless steel, plastic, etc.
Notes:	
1.1.1.7	Thermal Bridging/mitigation strategy identification: In the box below, Rater/Verifier has noted any thermal bridges in the assembly observed on the project and strategies used for mitigation. Describe and provide photo documentation where such details are missed.
Notes:	Describe any thermal bridges present and/or mitigation strategies:
1.1.2	Whole Building Airtightness Testing:
1.1.2.1	<b>Mid-Construction Airtightness Testing:</b> This is an optional, but recommend test. (This test is required for Phius Prescriptive Path projects.)
1.1.2.2	Final Airtightness Testing: If a Multifamily building, provide to Phius a Who Building Blower Door testing plan. Conduct multi-point blower door tests for depressurization and pressurization, following building set-up per Phius Certification Guidebook & ANSI/RESNET/ICC Std 380-2022. Enter data into the Building Envelope tab of the QA Workbook and upload testing plan & report i project folder: 4. PHIUS+ On-Site Verification.
Notes:	

#### Control Field Checklist, v24.1.1

(September 2025)		
City		_State
I - Building Envelope		
Site Photos R Code to view examples of site photos, Don'ts and Do's:		
s:	Rater/Verifie Confirmed	N/A
blies, to include measured insulation thickness and material type. Incl ea(s) insulated. Save photos into project folder: 4. PHIUS+ On-Site Veril		w context and
)		
or and exterior insulation as applicable)	+ +	+ +
d exterior insulation as applicable)	+ =	+ +
опетен применен из применен и		
	Rater/Verifie	r N/A
available. Include photos that show window installed, U-value, and SHO	Confirmed SC. Save photos into	project folde
RC data is not available, see requirements within the Key Documents ta		
low(s)		
Vindow(s)	<del>                                     </del>	
) ovie)	+ +	+ +
or(s)	<del>                                     </del>	<del>                                      </del>
doors (roof access, attic access, etc.)		
, , , , , , , , , , , , , , , , , , , ,		
	Rater/Verifie Confirmed	r N/A
building thermal envelope. Provide representative photos, including, is different photos, overhangs, and roofs. Include photos that indicate any them	but not limited to: a	
on.		
	+ +	+ +
	+ =	+ +
ditioned spaces		+ +
	Rater/Verifie Confirmed	r N/A
tion and significant architectural features including balconies, overhan icent to the building. Include photos that show any nearby structures,	gs and shading devi	
Save photos into project folder: 4. PHIUS+ On-Site Verification.		-8
ere applicable)	<del>                                     </del>	
levation	+ =	
acent obstructions	+ =	
acent obstructions		000000000000000000000000000000000000000

# phius Quality Control Field Checklist, v24.1.1

	(September 2025)			
1.1	Field Verification			
444	Rater/Verifier is responsible for verifying the tasks below have been	Rater/Verifier	N/A	PROG
1.1.1	Architectural Features, Insulation, and Thermal Bridging	Confirmed	N/A	REQ.
1.1.1.1	<b>Drawings Check:</b> Describe any significant variations in construction from the construction drawings and specifications (insulation, window sizes, window performance, fixed shading etc.).			ALL
Notes:				
1.1.1.2	Framing Inspection: Framing matches architectural plans (depth & spacing, e.g., 2x6 16" O.C.). If not, please describe in notes section below.			ALL
Notes:				
1.1.1.3	<b>Operable Shading:</b> If operable shading has been installed, describe operable shading.			ALL
Notes:				
1.1.1.4	<b>Insulation R-Value:</b> All insulation R-values match those listed on architectural plans. If not, please describe in notes section below.			ALL
Notes:				
1.1.1.5	<b>Insulation Quality Check:</b> All insulated assemblies have achieved a RESNET Grade I cavity insulation level, or alternatively Grade II with continuous insulation.			ENERGY STAR
Notes:				
1.1.1.6	Fastener Quality Check: In the box below, describe the material of fastener used to install exterior insulation (aluminum, mild steel, stainless steel, plastic, etc.).			Phius
Notes:				
1.1.1.7	Thermal Bridging/mitigation strategy identification: In the box below, Rater/Verifier has noted any thermal bridges in the assembly observed on the project and strategies used for mitigation. Describe and provide photo documentation where such details are missed.			Phius
Notes:	Describe any thermal bridges present and/or mitigation strategies:			
1.1.2	Whole Building Airtightness Testing:	Rater/Verifier Confirmed	N/A	PROG REQ.
1.1.2.1	Mid-Construction Airtightness Testing: This is an optional, but recommended test. (This test is required for Phius Prescriptive Path projects.)			
1.1.2.2	Final Airtightness Testing: If a Multifamily building, provide to Phius a Whole Building Blower Door testing plan. Conduct multi-point blower door tests for depressurization and pressurization, following building set-up per Phius Certification Guidebook & ANSI/RESNET/ICC Std 380-2022. Enter data into the Building Envelope tab of the QA Workbook and upload testing plan & report into project folder: 4. PHIUS+ On-Site Verification.			Phius
Notes:				



1.1.3	Compartmentalization Airtightness Testing:
1.1.3.1	Requirements: Required for Townhouse & multifamily dwelling units.
1.1.3.2	Compartmentalization Airtightness Testing: Conduct compartmentalization airtightness testing of individual dwelling units in accordance with Phius Guide and ANSI/RESNETI/CC Std 380-2022. The maximum air leakage shall be 0.3 CFM50/sq ft** of dwelling unit Envelope Surface Area. Enter results into the Building Envelope tab of the QA Workbook, and upload testing report into project folder: 4. PHIUS+ On-Site Verification.  ** Note 0.3 CFM50/sq ft shall be the target rate until such time EPA or DOE programs require a tighter value.
Notes:	

## y Control Field Checklist, v24.1.1

, , , , , , , ,			
Field Verification  Jer is responsible for verifying the tasks below have been to	completed:		
nsulation, and Thermal Bridging	Rater/Verifier Confirmed	N/A	PROG REQ.
significant variations in construction from the fications (insulation, window sizes, window			ALL
natches architectural plans (depth & spacing, e.g., ibe in notes section below.			ALL
hading has been installed, describe operable			ALL
n R-values match those listed on architectural otes section below.			ALL
sulated assemblies have achieved a RESNET Grade atively Grade II with continuous insulation.			ENERGY STAR
,			
box below, describe the material of fastener used ninum, mild steel, stainless steel, plastic, etc.).			Phius
trategy identification: In the box below, mal bridges in the assembly observed on the nitigation. Describe and provide photo ils are missed.			Phius
present and/or mitigation strategies:			
ess Testing:	Rater/Verifier Confirmed	N/A	PROG REQ.
Testing: This is an optional, but recommended us Prescriptive Path projects.)			
Multifamily building, provide to Phius a Whole  n. Conduct multi-point blower door tests for ion, following building set-up per Phius RESNET/ICC Std 380-2022. Enter data into the Workbook and upload testing plan & report into Verification.			Phius

# phius Quality Control Field Checklist, v24.1.1

1.1.3	Compartmentalization Airtightness Testing:	Verifier Confirmed	N/A	PROG REQ.
1.1.3.1	Requirements: Required for Townhouse & multifamily dwelling units.			
1.1.3.2	Compartmentalization Airtightness Testing: Conduct compartmentalization airtightness testing of individual dwelling units in accordance with Phius Guidebook and ANSI/RESNET/ICC Std 380-2022. The maximum air leakage shall be 0.3 CFM50/sq ft** of dwelling unit Envelope Surface Area. Enter results into the Building Envelope tab of the QA Workbook, and upload testing report into project folder: 4. PHIUS+ On-Site Verification.  ** Note 0.3 CFM50/sq ft shall be the target rate until such time EPA or DOE programs require a tighter value.			Phius
Notes:				



		(September 2025)
Projec	t #	Project NameCity
		2 – Ventilation
2.0		Site Photos  Scan QR Code to view examples of site photos, Don'ts and Do'
2.0.1	Site Phot	os of Ventilation Systems:
	ground loop) as Verification.	each installed ventilation system and auxiliary ventilation system defrost equipment ( nd nameplate (manufacturer, model number). Include photos that show context. Sav
2.0.1.1	HRV or ERV	
2.0.1.2	Auxiliary V	entilation Equipment
Notes:		
2.1		Field Verification Rater/Verifier is responsible for verifying the tasks below have
2.1.1	General:	
2.1.1.1	≥ 4' above g	air inlets and outlets for projects in Climate Zones 4-8 are installed grade and/or roof deck.
2.1.1.2		air comes directly from outdoors, not from adjacent dwelling units, aces, garages, crawlspaces, or attics.
2.1.1.3	Outside sup distribution	ply air passes through a minimum MERV 8 filter prior to
2.1.1.4	Filter is loca superintend	ted to facilitate regular service by the occupant and/or building dent.
2.1.1.5	fiberglass d retarder is o	or retarder is installed over all air-permeable insulation (such as uct wrap) on ventilation ducts connected to outside. Vapor continuous and sealed to building air barrier and ventilation unit s, breaks or holes.
2.1.2	Kitchens	:
2.1.2.1		haust register installed ≥ 6' from the nearest edge of the cooktop. string distance")
	Designate v	which type of filter was installed (either or is acceptable):
2.1.2.2	2.1.2.2.1	MERV 3+ filter for trapping grease at ERV/HRV exhaust register.
	2.1.2.2.2	Washable mesh filter for trapping grease in range hood.
	Installed ra	inge hood is one of the following (select one):
2.1.2.3	2.1.2.3.1	Recirculating hood over range.
	2.1.2.3.2	Range hood exhausted directly to outside.
	Measured l	kitchen direct exhaust rates meets one of the following (select
2.1.2.4	2.1.2.4.1	Meets Energy Star, IAP, and ZERH requirements for minimum kitchen exhaust airflow.
Notes:		

## Control Field Checklist, v24.1.1

(September 2025)

(September 2020)			
rtightness Testing:	Verifier Confirmed	N/A	PROG REQ.
vnhouse & multifamily dwelling units.			
ness Testing: Conduct compartmentalization by the line of the line			Phius

# phius Quality Control Field Checklist, v24.1.1

		(September 2025)			
Projec	t #	Project NameCity			State
		2 – Ventilation			
2.0		Site Photos Scan QR Code to view examples of site photos, Don'ts and Do's:			
2.0.1	Site Phot	os of Ventilation Systems:	Rater/Ver Confirm		N/A
	Take photos of ground loop) a Verification.	each installed ventilation system and auxiliary ventilation system defrost equipment (el nd nameplate (manufacturer, model number). Include photos that show context. Save p	ectric, hot water loop fr	om DHW	
2.0.1.1	HRV or ERV				
2.0.1.2	Auxiliary V	entilation Equipment			
Notes:					
2.1		Field Verification Rater/Verifier is responsible for verifying the tasks below have be	een completed:		
2.1.1	General:		Rater/Verifier Confirmed	N/A	PROG REQ.
2.1.1.1		air inlets and outlets for projects in Climate Zones 4-8 are installed grade and/or roof deck.			
2.1.1.2		air comes directly from outdoors, not from adjacent dwelling units, baces, garages, crawlspaces, or attics.			
2.1.1.3	Outside sup distribution	ply air passes through a minimum MERV 8 filter prior to			Phius
2.1.1.4	Filter is loca superintend	ited to facilitate regular service by the occupant and/or building dent.			Fillus
2.1.1.5	fiberglass d retarder is	or retarder is installed over all air-permeable insulation (such as uct wrap) on ventilation ducts connected to outside. Vapor continuous and sealed to building air barrier and ventilation unit s, breaks or holes.			
2.1.2	Kitchens		Rater/Verifier Confirmed	N/A	PROG REQ.
2.1.2.1		haust register installed ≥ 6' from the nearest edge of the cooktop. string distance")			
		which type of filter was installed (either or is acceptable):			
2.1.2.2	2.1.2.2.1	MERV 3+ filter for trapping grease at ERV/HRV exhaust register.			
	2.1.2.2.2	Washable mesh filter for trapping grease in range hood.			
	Installed ra	ange hood is one of the following (select one):			Phius
2.1.2.3	2.1.2.3.1	Recirculating hood over range.			
	2.1.2.3.2	Range hood exhausted directly to outside.			
	Measured	kitchen direct exhaust rates meets one of the following (select o	ne or more):		
2.1.2.4	2.1.2.4.1	Meets Energy Star, IAP, and ZERH requirements for minimum kitchen exhaust airflow.			
Notes:					

# phius Quality Control Field Chec

2.1.3	Bedroom	s:				
		Provision made to supply outdoor air to all bedrooms in dwelling units and 2.1.3.1.1 or 2.1.3.1.2. If complying with 2.1.3.1.1, skip to 2.1.3.2.				
	2.1.3.1.1		dicated outdoor air supply ventilation ductwork insideroms.	talled to all		
2.1.3.1	2.1.3.1.2	Ou he ple	utdoor air supply ventilation ductwork integrated wit ating/cooling ductwork and is connected directly to enum of the air handler (also complies with 2.1.3.1.2 1.3.1.2.2).	the return		
	2.1.3.1.2	2.1	ERV/HRV remains in balance under all fan speeds of heating/cooling air handler.			
	2.1.3.1.	2.2	Air handler fan designed to run continuously by de handler power (Watts) added to ventilation power calculation of W/cfm, and meets DOE ZERH efficac requirements.	(Watts), in		
2.1.3.2	difference o	f+/-	ressure balanced to achieve a Rater/Verifier measu 1 Pa with respect to the main body of the dwelling are closed and only the ventilation system is operat	unit when al		
Notes:						
2.1.4	Bathroon	ns:				
2.1.4.1	Measured I 2.1.4.1.1 2.1.4.1.2	≥2	aroom exhaust rates meets one of the following Ocfm continuous. O cfm intermittent.	(select one)		
2.1.5			Auxiliary Systems:			
2.1.5.1	tank, ground	d loc	er type of ERV/HRV defrost - electric, hot water loop f op into the Ventilation tab of the Workbook.			
2.1.5.2			s demonstrated the defrost control logic is set up pr	roperly. Rater/Verifi		
2.1.6			System Airflow Testing:	Confirme		
2.1.6.1	ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.					
2.1.6.2	Conduct ver Ventilation t	ntila tab d	ust Ventilation System Airflow Testing: tion system airflow testing, enter data into of QA Workbook, and if available, provide testing ect folder: 4. PHIUS+ On-Site Verification.			
Notes:						

## Control Field Checklist, v24.1.1

(September 2025)

City				State
2 – Ventilation				
Site Photos de to view examples of site photos, Don'ts and Do's:				
Systems:		Rater/Ver		N/A
stem and auxiliary ventilation system defrost equipment (ele			om DHV	
r, model number). Include photos that show context. Save	photos	into project fold	ier: 4. PH	IIUS+ On-Site
t				
Field Verification				
er is responsible for verifying the tasks below have l				
		er/Verifier onfirmed	N/A	PROG REQ.
or projects in Climate Zones 4-8 are installed				
n outdoors, not from adjacent dwelling units,				1
aces, or attics.				]
a minimum MERV 8 filter prior to				
r service by the occupant and/or building				Phius
over all air-permeable insulation (such as				1
n ducts connected to outside. Vapor to building air barrier and ventilation unit				
	Rat	er/Verifier	N/A	PROG
d > C) from the possest edge of the coelston	C	onfirmed	IWA	REQ.
d ≥ 6' from the nearest edge of the cooktop.				
as installed (either or is acceptable):				
pping grease at ERV/HRV exhaust register.				
r for trapping grease in range hood.				
ne following (select one):				Phius
ver range.				
ed directly to outside.				
st rates meets one of the following (select o	ne or	more):		
AP, and ZERH requirements for minimum ow.				

# phius Quality Control Field Checklist, v24.1.1

(September 2025)

Provision made to supply outdoor air to all bedrooms in dwelling units and comply with either			(September 2025)			
2.1.3.1.1 or 2.1.3.1.2. If complying with 2.1.3.1.1. skip to 2.1.3.2.  2.1.3.1.1 bedrooms.  Outdoor air supply ventilation ductwork installed to all bedrooms.  Outdoor air supply ventilation ductwork integrated with heating/cooling ductwork and is connected directly to the return plenum of the air handler (also complies with 2.1.3.1.2.1 and 2.1.3.1.2.2).  2.1.3.1.2.1 ERW/HRV remains in balance under all fan speeds of the heating/cooling air handler.  Air handler fan designed to run continuously by default. Air handler fan designed to run continuously by default. Air handler power (Watts) added to ventilation power (Watts), in calculation of Wicfm, and meets DOE ZERH efficacy requirements.  Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4.1 Bathrooms:  Rater/Verifier Confirmed N/A REQ.  2.1.4.1 2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  Rater/Verifier Confirmed N/A REQ.  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  ERV/HRV Ventilation System Airflow Testing: Confirmed Confirmed N/A REQ.  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.3	Bedroom	s:		N/A	
2.1.3.1.1 Dedicated outdoor air supply ventilation ductwork installed to all bedrooms.  2.1.3.1.2 Outdoor air supply ventilation ductwork integrated with heating/cooling ductwork and is connected directly to the return plenum of the air handler (also complies with 2.1.3.1.2.1 and 2.1.3.1.2.2).  2.1.3.1.2.1 ERW/HRV remains in balance under all fan speeds of the heating/cooling air handler.  Air handler fan designed to run continuously by default. Air handler power (Watts) added to ventilation power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.  Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4.1 Bathrooms:  Rater/Verifier N/A PROG. REQ. 2.1.4.1.1 ≥20cfm continuous.  2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  Rater/Verifier Confirmed Conf					er	
2.1.3.1.1 bedrooms.  Outdoor air supply ventilation ductwork integrated with heating/cooling ductwork and is connected directly to the return plenum of the air handler (also complies with 2.1.3.1.2.1 and 2.1.3.1.2.2).  2.1.3.1.2.1 ERWHRV remains in balance under all fan speeds of the heating/cooling air handler.  Air handler fan designed to run continuously by default. Air handler power (Watts) added to ventilation power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.  Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4 Bathrooms:  Rater/Verifier Confirmed  Measured bathroom exhaust rates meets one of the following (select one):  2.1.4.1 2.1.4.1.1 220cfm continuous.  2.1.4.1.2 250 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  If installed, enter type of ERW/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  Philus  Philus  Rater/Verifier Confirmed  N/A REQ.  2.1.5.1 Project team has demonstrated the defrost control logic is set up properly.  ERV/HRV Ventilation System Airflow Testing:  Confirmed  Confirmed  Confirmed  REQ.  PROG.  REQ.  Philus		2.1.3.1.1 or				
2.1.3.1.2   heating/cooling ductwork and is connected directly to the return plenum of the air handler (also compiles with 2.1.3.1.2.1 and 2.1.3.1.2.1		2.1.3.1.1	11.2	all		
2.1.3.1.2   heating/cooling ductwork and is connected directly to the return plenum of the air handler (also complies with 2.1.3.1.2.1 and 2.1.3.1.2.2)   2.1.3.1.2.1   ERV/HRV remains in balance under all fan speeds of the heating/cooling air handler.  2.1.3.1.2.2   Landler power (Watts) added to ventilation power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.  2.1.3.2   Bedrooms are pressure balanced to achieve a Rater/Verifler measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4   Bathrooms:   Rater/Verifler Confirmed   N/A PROGRED   REQ.   Start   Rater/Verifler   Reg.   Reg.			Outdoor air supply ventilation ductwork integrated with			
2.1.3.1.2.1.2.2).  2.1.3.1.2.1.2.2).  2.1.3.1.2.2.3. ERW/HRV remains in balance under all fan speeds of the heating/cooling air handler.  Air handler fan designed to run continuously by default. Air handler power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.  Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4.1 Bathrooms:  Reconfirmed  Measured bathroom exhaust rates meets one of the following (select one):  2.1.4.1 ≥20cfm continuous.  2.1.4.1.2 ≥50 cfm intermittent.  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW ank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6.1 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing:  Condirmed  Confirmed  PROG  REQ.  PROG  REQ.  PROG  REQ.  PROG  REQ.  PROG  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  PROG  REQ.  PROG  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  PROG  PROG  REQ.  PROG  Confirmed	2424	2.1.3.1.2	heating/cooling ductwork and is connected directly to the retur	rn 🔲		
2.1.3.1.2.1   heating/cooling air handler.	2.1.3.1		2.1.3.1.2.2).			
Air handler fan designed to run continuously by default. Air handler power (Watts) added to ventilation power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.  Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  Notes:  2.1.4 Bathrooms:  Measured bathroom exhaust rates meets one of the following (select one):  2.1.4.1 2.20cfm continuous.  2.1.4.1.1 2.20cfm continuous.  2.1.4.1.2 2.50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  Rater/Verifier Confirmed  Star  Confirmed  N/A PROG REQ.  Energy Star  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Phius  Ph		2.1.3.1.	2.1			Phius
Andler power (Watts) added to ventilation power (Watts), in calculation of W/cfm, and meets DOE ZERH efficacy requirements.    Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.    Notes:     Rater/Verifier confirmed   N/A people   N/A				ir		
Calculation of W/cfm, and meets DOE ZERH efficacy requirements.   Calculation of W/cfm, and meets DOE ZERH efficacy requirements.   Calculation System balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.   Calculation System airflow Testing:   Calculation System Airflow Testing:   Calculation System Airflow Testing:   Calculation Calculation System Airflow Testing:   Calculation Calculation Calculation System Airflow Testing:   Calculation		2121	handler power (Watts) added to ventilation power (Watts),	in		
Bedrooms are pressure balanced to achieve a Rater/Verifier measured pressure difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.    Notes:   Rater/Verifier Confirmed REQ.		2.1.5.1.	calculation of W/cfm, and meets DOE ZERH efficacy			
2.1.3.2 difference of +/- 1 Pa with respect to the main body of the dwelling unit when all bedroom doors are closed and only the ventilation system is operating at design speed.  2.1.4.1 Bathrooms:  2.1.4.1 ≥20cfm continuous.  2.1.4.1.1 ≥20cfm continuous.  2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW ank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing:  Condiurt ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing:  Conduct ventilation system airflow testing, enter data into Ventilation to of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.		Bedrooms a		sure		
bedroom doors are closed and only the ventilation system is operating at design speed.  2.1.4. Bathrooms:    Rater/Verifier Confirmed REQ.	2122		·	en all		
Notes:	2.1.3.2		ors are closed and only the ventilation system is operating at de	esign	-	
2.1.4 Bathrooms:    Measured bathroom exhaust rates meets one of the following (select one):   2.1.4.1.1   ≥20cfm continuous.   2.1.4.1.2   ≥50 cfm intermittent.   Rater/Verifier Confirmed   N/A PROGREQ.   Star		speed.				
2.1.4.1 ≥ 20cfm continuous.  2.1.4.1.1 ≥ 20cfm continuous.  2.1.4.1.2 ≥ 50 cfm intermittent.  2.1.5.1 Ventilation Auxiliary Systems:  If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing:  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  PROG  REQ.  PROG  REQ.  PROG  REQ.  PROG  REQ.  PROG  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Confirmed  Philus  Philus  Philus  Philus  Philus  Philus  Philus  Philus  Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	Notes:					
2.1.4.1 ≥20cfm continuous.  2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  2.1.6.1 ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation tab of QA Workbook, and if available, provide testing report into ventilation	2.1.4	Bathroor	ns:		N/A	
2.1.4.1.1 ≥2.0cm continuous.  2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  Rater/Verifier Confirmed  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.		Measured	oathroom exhaust rates meets one of the following (select o	ne):		Energy
2.1.4.1.2 ≥50 cfm intermittent.  2.1.5 Ventilation Auxiliary Systems:  Rater/Verifier Confirmed  2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  Rater/Verifier Confirmed  Rater/Verifier Confirmed  PROG REQ.  PROG REQ.  2.1.6.1 GRATER/Verifier Confirmed  Rater/Verifier Confirmed  PROG REQ.  PROG REV.  PROG REQ.  PROG REQ.  PROG REQ.  PROG REQ.  PROG REQ.  PROG REV.  PROG REV	2.1.4.1					
2.1.5.1 If installed, enter type of ERV/HRV defrost - electric, hot water loop from DHW tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Phius  Phius  PROG REQ.  PROG REQ.  PROG Confirmed  OA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.		2.1.4.1.2	≥50 cfm intermittent.			
2.1.6.1 tank, ground loop into the Ventilation tab of the Workbook.  2.1.5.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5	Ventilati		B-101-181	_	
2.1.6.2 Project team has demonstrated the defrost control logic is set up properly.  2.1.6 Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Phius  Phius				Confirmed	N/A	
2.1.6. Ventilation System Airflow Testing:  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.1		enter type of ERV/HRV defrost - electric, hot water loop from DH\	Confirmed		REQ.
2.1.6.1  ERV/HRV Ventilation System Airflow Testing:  Confirmed Confirmed N/A REQ.  ERV/HRV Ventilation System Airflow Testing: Conduct ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.		tank, groun	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.	Confirmed		REQ.
ventilation system airflow testing. Enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	tank, groun Project tear	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook. n has demonstrated the defrost control logic is set up properly.	Confirmed W		REQ. Phius
of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	tank, groun Project tean Ventilati	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In System Airflow Testing:  Rater/V Confir	Confirmed W Grifier Builder		REQ. Phius PROG
project folder: 4. PHIUS+ On-Site Verification.  Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	tank, groun Project tean Ventilation	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook. In has demonstrated the defrost control logic is set up properly. On System Airflow Testing:  entilation System Airflow Testing: Conduct	Confirmed W Grifier Builder		REQ. Phius PROG
Auxiliary Exhaust Ventilation System Airflow Testing: Conduct ventilation system airflow testing, enter data into Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	Ventilations	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook. In has demonstrated the defrost control logic is set up properly.  On System Airflow Testing:  Confirentilation System Airflow Testing: Conduct system airflow testing. Enter data into Ventilation tab	Confirmed  W  Gerifier Builder  Confirmed  Confirmed	N/A	REQ. Phius PROG
Ventilation tab of QA Workbook, and if available, provide testing report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	tank, groun Project team Ventilation ERV/HRV Ventilations of QA Work	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In System Airflow Testing:  Confirmentilation System Airflow Testing: Conduct system airflow testing. Enter data into Ventilation tab book, and if available, provide testing report into	Confirmed  W  Gerifier Builder  Confirmed  Confirmed	N/A	Phius PROG REQ.
report into project folder: 4. PHIUS+ On-Site Verification.	2.1.5.2	tank, groun Project tean Ventilati ERV/HRV V ventilations of QA Work project fold Auxiliary E	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook. In has demonstrated the defrost control logic is set up properly.  ON System Airflow Testing:  entilation System Airflow Testing: Conduct system airflow testing. Enter data into Ventilation tab book, and if available, provide testing report into er: 4. PHIUS+ On-Site Verification.  Schaust Ventilation System Airflow Testing:	Confirmed  W  Gerifier Builder  Confirmed  Confirmed	N/A	Phius PROG REQ.
	2.1.5.2 2.1.6 2.1.6.1	tank, groun Project tean Ventilati ERV/HRV V ventilations of QA Work project fold Auxiliary E Conduct ver	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  Rater/V Confirmation System Airflow Testing:  In the control of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In the control of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In the control of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In the control of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In the control of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook.  In has demonstrated the defrost control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logic is set up properly.  In the workbook control logi	Verifier Builder Confirmed	N/A	Phius PROG REQ.
Notes:	2.1.5.2 2.1.6 2.1.6.1	tank, groun Project tear Ventilati ERV/HRV V ventilation of QA Work project fold Auxiliary E Conduct ver Ventilation of	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  Rater/V Confiremaillation System Airflow Testing:  In the control of the workbook and if available, provide testing that into tab of QA Workbook, and if available, and tab of QA Workbook, and if available, and tab of QA Workbook, and if available that into tab of QA Workbook, and if available that into tab of QA Work	Verifier Builder Confirmed	N/A	Phius PROG REQ.
	2.1.5.2 2.1.6 2.1.6.1	tank, groun Project tear Ventilati ERV/HRV V ventilation of QA Work project fold Auxiliary E Conduct ver Ventilation of	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  Rater/V Confiremaillation System Airflow Testing:  In the control of the workbook and if available, provide testing that into tab of QA Workbook, and if available, and tab of QA Workbook, and if available, and tab of QA Workbook, and if available that into tab of QA Workbook, and if available that into tab of QA Work	Verifier Builder Confirmed	N/A	Phius PROG REQ.
	2.1.5.2 2.1.6 2.1.6.1 2.1.6.2	tank, groun Project tear Ventilati ERV/HRV V ventilation of QA Work project fold Auxiliary E Conduct ver Ventilation of	enter type of ERV/HRV defrost - electric, hot water loop from DHV d loop into the Ventilation tab of the Workbook.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  In has demonstrated the defrost control logic is set up properly.  Rater/V Confiremaillation System Airflow Testing:  In the control of the workbook and if available, provide testing that into tab of QA Workbook, and if available, and tab of QA Workbook, and if available, and tab of QA Workbook, and if available that into tab of QA Workbook, and if available that into tab of QA Work	Verifier Builder Confirmed	N/A	Phius PROG REQ.



Projec	t # Project Name City City
	3 – Heating & Cooling
3.0	Site Photos  Scan QR Code to view examples of site photos, Don'ts and Do's:
3.0.1	Site Photos of Heating & Cooling Systems:
	Take photos of each installed heating & cooling system and nameplate (manufacturer, model number). nameplate. Save photos into project folder: 4. PHIUS+ On-Site Verification.
3.0.1.1	Heating & Cooling System
Notes	
3.1	Field Verification  Rater/Verifier is responsible for verifying the tasks below have be
3.1.1	Combustion Equipment:
3.1.1.1	If combustion equipment for space heating is included in the project, provide a dedicated branch circuit, in compliance with DOE ZERH v2 NPR Exhibit 1, Item 11. Branch circuit shall be labeled "For Future Heat Pump Space Conditioning."
3.1.1.2	Combustion furnaces, boilers and/or water heaters located within the buildings' pressure boundary are sealed combustion, direct-vent appliances.
3.1.1.3	Natural draft fireplaces are not installed.
3.1.1.4	Installed woodstoves have a combustion air inlet connected to the firebox.
3.1.2	Controls:
3.1.2.1	Heating/Cooling System Fan - air flow is produced when thermostat is set to "fan on", Heated air flow is produced when thermostat is set to "Heat", Cooling air flow is produced when thermostat is set to "Cool".
3.1.3	Condensation Management:
3.1.3.1	Ensure condensate drain provided for cooling system evaporator coil or a condensate drain is located within 3 feet.
3.1.3.2	Corrosion-resistant drain pan, properly sloped to drainage system is included with each HVAC component that produces condensate.
3.1.4	Distribution System Layout:
3.1.4.1	Duct installation reasonably matches design layout.
3.1.5	Heating/Cooling Distribution System Testing:
3.1.5.1	<b>Ducted Heating/Cooling Distribution System Testing:</b> Conduct leakage testing and balancing of ducted heating/cooling distribution system, enter data into Heat & Cool tab of QA Workbook. Provide TAB report into project folder: 4. PHIUS+ On-Site Verification.
3.1.5.2	Hydronic Heating/Cooling Distribution System Testing: Collect documentation of testing of hydronic heating/cooling distribution system, enter data into Heat & Cool tab of QA Workbook, and provide report into project folder: 4. PHIUS+ On-Site Verification.
Notes:	

#### ty Control Field Checklist, v24.1.1

(September 2025)					
		Rater/Verifier Confirmed	N/A	PROG REQ.	
tdoor air to all bedrooms in dwelli	mply with eith	er			
lying with 2.1.3.1.1, skip to 2.1.3.2.					
or air supply ventilation ductwork ins	talled to all				
oly ventilation ductwork integrated wiductwork and is connected directly to r handler (also complies with 2.1,3,1,2					
nains in balance under all fan speeds					
ing air handler.	or are			Phius	
an designed to run continuously by de er (Watts) added to ventilation power f W/cfm, and meets DOE ZERH efficac s.	(Watts), in				
ced to achieve a Rater/Verifier measu pect to the main body of the dwelling d only the ventilation system is opera					
		Rater/Verifier Confirmed	N/A	PROG REQ.	
it rates meets one of the following	(select one):		N/A	REQ.	
st rates meets one of the following	(select one):		N/A	REQ. Energy	
	(select one):	Confirmed	N/A	REQ. Energy Star	
us.	(select one):		N/A	REQ. Energy	
us. tent.		Confirmed  Rater/Verifier		REQ. Energy Star PROG	
rus. tent. /stems: HRV defrost - electric, hot water loop t	from DHW	Confirmed  Rater/Verifier Confirmed	N/A	REQ. Energy Star PROG REQ.	
us. tent. /stems: HRV defrost - electric, hot water loop f ntilation tab of the Workbook.	from DHW	Confirmed  Rater/Verifier Confirmed	N/A	REQ. Energy Star PROG REQ.	
us. tent. / <b>stems:</b> HRV defrost - electric, hot water loop h ntilation tab of the Workbook. Ed the defrost control logic is set up p	from DHW roperly. Rater/Verifier	Confirmed  Rater/Verifier Confirmed  Builder	N/A	REQ. Energy Star PROG REQ. Phius PROG REQ.	
tus.  Itent.  If the state of the water loop for th	from DHW roperly. Rater/Verifier	Rater/Verifier Confirmed  Builder Confirmed	N/A N/A	REQ. Energy Star PROG REQ. Phius	

## phius Quality Control Field Checklist, v24.1.1

(September 2025) Project Name Project # State 3 - Heating & Cooling Site Photos 3.0 Scan QR Code to view examples of site photos, Don'ts and Do's: Rater/Verifier Site Photos of Heating & Cooling Systems: N/A Confirmed Take photos of each installed heating & cooling system and nameplate (manufacturer, model number). Include photos that show equipment and nameplate. Save photos into project folder: 4. PHIUS+ On-Site Verification 3.0.1.1 Heating & Cooling System Notes Field Verification 3.1 Rater/Verifier is responsible for verifying the tasks below have been completed: **PROG** Combustion Equipment: Confirmed REQ. If combustion equipment for space heating is included in the project, provide a 3.1.1.1 dedicated branch circuit, in compliance with DOE ZERH v2 NPR Exhibit 1, Item 11. Branch circuit shall be labeled "For Future Heat Pump Space Conditioning." Combustion furnaces, boilers and/or water heaters located within the Phius buildings' pressure boundary are sealed combustion, direct-vent appliances. 3.1.1.3 Natural draft fireplaces are not installed. 3.1.1.4 Installed woodstoves have a combustion air inlet connected to the firebox. PROG Rater/Verifier N/A Controls: Confirmed REQ. Heating/Cooling System Fan - air flow is produced when thermostat is set to "fan on", Heated air flow is produced when thermostat is set to "Heat", Cooling Phius air flow is produced when thermostat is set to "Cool" Rater/Verifier PROG Condensation Management: N/A REQ. Confirmed Ensure condensate drain provided for cooling system evaporator coil or a condensate drain is located within 3 feet. Phius Corrosion-resistant drain pan, properly sloped to drainage system is included with each HVAC component that produces condensate Rater/Verifier PROG N/A Distribution System Layout: Confirmed REQ. 3.1.4.1 Duct installation reasonably matches design layout. Phius PROG Rater/Verifier Heating/Cooling Distribution System Testing: N/A Confirmed REQ. Ducted Heating/Cooling Distribution System Testing: Conduct leakage testing and balancing of ducted heating/cooling distribution system, enter data into Heat & Cool tab of QA Workbook. Provide TAB report into project folder: 4. PHIUS+ On-Site Verification. Phius Hydronic Heating/Cooling Distribution System Testing: Collect documentation of testing of hydronic heating/cooling distribution system, enter data into Heat & Cool tab of QA Workbook, and provide report into project folder: 4. PHIUS+ On-Site Verification. Notes:

## phius Quality Control Field Che

	Project Name	City
	4 – Don	nestic Hot Wate
		ite Photos examples of site photos, Don'ts and l
Site Pho	otos of Domestic Hot Wate	er System:
Recircula	tion Pump and Controls (if appl	icable)
		ield Verification sible for verifying the tasks below ho
Domest	tic Hot Water System:	
	3	matches design layout. Describe
	ollowing are met:	<u> </u>
4.1.1.3.1	Requirements or DOE ZERH Mult	
		eater capacity is greater than
4.1.1.4.1	Provided a branch circuit sized for	or an electric appliance, equipme city that terminates within 6 feet
	Domestic Recircular Pipe insta difference water effi	Site Photos of Domestic Hot Water  Take photos of each installed domestic hot water system photos into project folder: 4. PHIUS+ On-Site Verification  Domestic Hot Water Heater  Recirculation Pump and Controls (if applied in the project folder: 4. PHIUS+ On-Site Verification  Domestic Hot Water Heater  Rater/Verifier is respons  Domestic Hot Water System:  Pipe installation and insulation reasonably in differences below:  An on-demand recirculation system for DHV water efficiency requirements. Describe and lift combustion water heating and water heating is met:  Provided a branch circuit sized feend use with an equivalent capa

#### ity Control Field Checklist, v24.1.1

(September 2025) City State 3 - Heating & Cooling Site Photos QR Code to view examples of site photos, Don'ts and Do's: & Cooling Systems: N/A Confirmed folder: 4. PHIUS+ On-Site Verification **Field Verification** Verifier is responsible for verifying the tasks below have been completed: PROG N/A Confirmed REQ. space heating is included in the project, provide a ompliance with DOE ZERH v2 NPR Exhibit 1, Item peled "For Future Heat Pump Space Conditioning." s and/or water heaters located within the Phius y are sealed combustion, direct-vent appliances. ot installed. combustion air inlet connected to the firebox. Rater/Verifier PROG N/A REQ. air flow is produced when thermostat is set to Phius roduced when thermostat is set to "Heat", Cooling ermostat is set to "Cool". Rater/Verifier PROG N/A ement: REQ. Confirmed ovided for cooling system evaporator coil or a Phius n, properly sloped to drainage system is included that produces condensate. Rater/Verifier PROG N/A ayout: REQ. Confirmed matches design layout. Phius Rater/Verifier PROG ibution System Testing: N/A Confirmed REQ. stribution System Testing: Conduct leakage ted heating/cooling distribution system, enter data orkbook. Provide TAB report into project folder: 4. Phius Distribution System Testing: Collect hydronic heating/cooling distribution system, ab of QA Workbook, and provide report into -Site Verification.

# phius Quality Control Field Checklist, v24.1.1

Project # Project Name City State 4 - Domestic Hot Water Site Photos Scan QR Code to view examples of site photos, Don'ts and Do's: 4.0.1 Site Photos of Domestic Hot Water System: photos into project folder: 4. PHIUS+ On-Site Verification. 4.0.1.1 Domestic Hot Water Heater 4.0.1.2 | Recirculation Pump and Controls (if applicable) Notes: **Field Verification** Rater/Verifier is responsible for verifying the tasks below have been completed: **Domestic Hot Water System:** Pipe installation and insulation reasonably matches design layout. Describe any Phius 4.1.1.1 differences below: Notes: An on-demand recirculation system for DHW was installed per DOE ZERH hot ZERH 4.1.1.2 water efficiency requirements. Describe any differences below Notes: If combustion water heating and water heater capacity is less than or equal to 300,000 Btu/hr (88 4.1.1.3 Complies with DOE ZERH Single Family Homes National Program 4.1.1.3.1 Requirements or DOE ZERH Multifamily National Program Requirements, Sections 10.1 and 10.2 in the Rater Field Checklist. Phius If combustion water heating and water heater capacity is greater than 300,000 Btu/hr (88 kW) the 4.1.1.4 Provided a branch circuit sized for an electric appliance, equipment or 4.1.1.4.1 end use with an equivalent capacity that terminates within 6 feet of the appliance or equipment. Notes:

## phius Quality Control Field Che

Project #

(September 2025)
Project Name

Project #	FProject NameCity
	5 – Appliances & Electrical L
5.0	Site Photos  Scan QR Code to view examples of site photos, Don'ts and D
5.0.1	Site Photos of Appliances
	Take photos of each installed appliance and nameplate (manufacturer, model number). Include project folder: 4. PHIUS+ On-Site Verification.
5.0.1.1	Refrigerator/Freezer/Wine Cooler
5.0.1.2	Dishwasher
5.0.1.3	Clothes Washer
5.0.1.4	Clothes Dryer
5.0.1.5	Range/Oven Combination
5.0.1.6	Wall Oven
5.0.1.7	Cooktop
5.0.1.8	Exhaust Range Hood
5.0.1.9	Miscellaneous (e.g., Dehumidifier)
5.0.1.10	Non-residential project or non-residential portion of a mixed-use projet Take photos of equipment and nameplate of all office equipment, kitch equipment, and process loads listed during design certification in the load Certification Feedback Form (consult with CPHC), documenting any chadditions, or deletions.
Notes:	
5.1	Field Verification  Rater/Verifier is responsible for verifying the tasks below ha
5.1.1	Combustion Appliances & Equipment:
5.1.1.1	Combustion Clothes Dyer: If combustion clothes drying. A dedicated 240- volt branch circuit with a minimum capacity of 30 amps shall terminate within 6 feet of natural gas clothes dryers and shall be accessible with no obstructions. Both ends of the branch circuit shall be labeled with the word "For Future Electric Clothes Drying" and be electrically isolated.
5.1.1.2	Combustion Cooking: If combustion cooking. A dedicated 240-Volt, 40A branch circuit shall terminate within 6 feet of natural gas ranges, cooktops and ovens and be accessible with no obstructions. Both ends of the branch circuit shall be labeled with the words "For Future Electric Range" and be electrically isolated.
5.1.1.3	Other Combustion Equipment: All combustion equipment shall be provided with a branch circuit sized for an electric appliance, equipment or end use with an equivalent capacity that terminates within 6 feet of the appliance or equipment.
Notes:	

#### y Control Field Checklist, v24.1.1

(September 2025) City State\_ - Domestic Hot Water **Site Photos** Code to view examples of site photos, Don'ts and Do's: **Hot Water System:** rols (if applicable) **Field Verification** ifier is responsible for verifying the tasks below have been completed: reasonably matches design layout. Describe any Phius stem for DHW was installed per DOE ZERH hot ZERH Describe any differences below: and water heater capacity is less than or equal to 300,000 Btu/hr (88 ZERH Single Family Homes National Program E ZERH Multifamily National Program ons 10.1 and 10.2 in the Rater Field Checklist. and water heater capacity is greater than 300,000 Btu/hr (88 kW) the ircuit sized for an electric appliance, equipment or ivalent capacity that terminates within 6 feet of 

## phius Quality Control Field Checklist, v24.1.1

	(September 2025)				
Project #					State
	5 – Appliances & Electrical Lo	ads			
5.0	Site Photos  Scan QR Code to view examples of site photos, Don'ts and Do's:				
5.0.1	Site Photos of Appliances		ater/Vei Confirm		N/A
	Take photos of each installed appliance and nameplate (manufacturer, model number). Include pho project folder: 4, PHIUS+ On-Site Verification.				otos into
5.0.1.1	Refrigerator/Freezer/Wine Cooler				
5.0.1.2	Dishwasher				
5.0.1.3	Clothes Washer				
5.0.1.4	Clothes Dryer				
5.0.1.5	Range/Oven Combination				
5.0.1.6	Wall Oven				
5.0.1.7	Cooktop				
5.0.1.8	Exhaust Range Hood				
5.0.1.9	Miscellaneous (e.g., Dehumidifier)				
5.0.1.10	Non-residential project or non-residential portion of a mixed-use project Take photos of equipment and nameplate of all office equipment, kitche equipment, and process loads listed during design certification in the Des Certification Feedback Form (consult with CPHC), documenting any change additions, or deletions.	n sign			
Notes:					
5.1	Field Verification  Rater/Verifier is responsible for verifying the tasks below have l	been comp	leted:		
5.1.1	Combustion Appliances & Equipment:	Rater/Ve Confir		N/A	PROG REQ.
5.1.1.1	Combustion Clothes Dyer: If combustion clothes drying. A dedicated 240- volt branch circuit with a minimum capacity of 30 amps shall terminate within 6 feet of natural gas clothes dryers and shall be accessible with no obstructions. Both ends of the branch circuit shall be labeled with the words "For Future Electric Clothes Drying" and be electrically isolated.				
5.1.1.2	Combustion Cooking: If combustion cooking. A dedicated 240-Volt, 40A branch circuit shall terminate within 6 feet of natural gas ranges, cooktops and ovens and be accessible with no obstructions. Both ends of the branch circuit shall be labeled with the words "For Future Electric Range" and be electrically isolated.				Phus
5.1.1.3	Other Combustion Equipment: All combustion equipment shall be provided with a branch circuit sized for an electric appliance, equipment or end use with an equivalent capacity that terminates within 6 feet of the appliance or equipment.				
Notes:					

# phius Quality Control Field Che

(September 2025)

5.1.2 All Other Appliances and Electrical Equipment

5.1.2.1 Appliances: Record Manufacturer and Model Number in the Appliances & Electrical tab of the QA Workbook.

5.1.2.2 Direct Exhaust Range Hood: Measure exhaust cfm and record this value int the Ventilation tab of the QA Workbook.

5.1.2.3 Electrical: Record any other significant energy use loads in the Appliances & Electrical Loads tab of the QA Workbook.

Notes:

5.1.3 Lighting

5.1.3.1 Lighting: Installed lighting matches lighting plan - describe variations, if applicable.

Notes:

## Control Field Checklist, v24.1.1

(September 2025)				
iances & Electrical Lo	ade	<u> </u>		State
Site Photos				
e to view examples of site photos, Don'ts and Do's	·	Rater/Ve Confirn		N/A
id nameplate (manufacturer, model number). Include ph on.	otos that	show context	. Save ph	iotos into
ier) -residential portion of a mixed-use project nameplate of all office equipment, kitche listed during design certification in the De onsult with CPHC), documenting any chan	en esign			
Field Verification	been co	mpleted:		
Equipment:	Rate	r/Verifier nfirmed	N/A	PROG REQ.
mbustion clothes drying. A dedicated 240- m capacity of 30 amps shall terminate expers and shall be accessible with no anch circuit shall be labeled with the words g" and be electrically isolated.				
stion cooking. A dedicated 240-Volt, 40A hin 6 feet of natural gas ranges, cooktops no obstructions. Both ends of the branch rords "For Future Electric Range" and be				Phus
All combustion equipment shall be sed for an electric appliance, equipment or city that terminates within 6 feet of the				

# phius Quality Control Field Checklist, v24.1.1

(September 2025)

5.1.2	All Other Appliances and Electrical Equipment	Rater/Verifier Confirmed	N/A	PROG REQ.
5.1.2.1	<b>Appliances:</b> Record Manufacturer and Model Number in the Appliances & Electrical tab of the QA Workbook.			DOE ZERH
5.1.2.2	<b>Direct Exhaust Range Hood:</b> Measure exhaust cfm and record this value into the Ventilation tab of the QA Workbook.			Dhive
5.1.2.3	<b>Electrical:</b> Record any other significant energy use loads in the Appliances & Electrical Loads tab of the QA Workbook.			Phius
Notes:				
5.1.3	Lighting	Rater/Verifier Confirmed	N/A	PROG REQ.
5.1.3.1	<b>Lighting:</b> Installed lighting matches lighting plan - describe variations, if applicable.			Phius
Notes:				

(phius	Quality Control Field C	h
--------	-------------------------	---

	(September 2025)
Project	# Project Name City
	6 – Renewables & Electrific
6.0	Site Photos Scan QR Code to view examples of site photos, Don'ts and D
6.0.1	Site Photos of Renewables & Electrification:
	Take photos that document the renewables and electrification. Include photos that show contex Site Verification.
6.0.1.1	Solar PV Installed (take photos of inverters and panels).
6.0.1.2	Electric Vehicle Ready (take photos of electric service panel identifying branch circuit as "Electric Vehicle Charging").
6.0.1.3	Electric Vehicle Supply Equipment (EVSE) (take photos of EV charger or charging station(s)).
Notes:	
6.1	Field Verification  Rater/Verifier is responsible for verifying the tasks below ha
6.1.1	Renewable Energy Systems:
6.1.1.1	Solar Thermal System: Installed solar PV system corresponds with shop drawings or purchase order, and document in the Renewables & Electrification tab of the QA Workbook.
6.1.1.2	Solar Photovoltaic System: Installed solar PV system corresponds with shop drawings or purchase order, and document in the Renewables & Electrification tab of the QA Workbook.
6.1.2	Electric Vehicle (EV) Charging Infrastructure:
6.1.1.2	Electric Vehicle (EV) Charging Infrastructure: Where parking spaces are provided, installed electric vehicle infrastructure corresponds with shop drawings and achieves the requirements listed in Section 1.3.4.3 of the Phius Guidebook v 24.1.0.
6.1.1.3	For non-residential projects and non-residential parts of mixed-use project, document EV Charging Infrastructure in the Renewables & Electrification tal of the QA Workbook.
Notes:	
Rater/	Verifier Name (Printed):
Signati	ure:
Date:	

## y Control Field Checklist, v24.1.1

d Electrical Equipment	Rater/Verifier Confirmed	N/A	PROG REQ.			
er and Model Number in the Appliances & c.			DOE ZERH			
easure exhaust cfm and record this value into kbook.			Dhius			
ificant energy use loads in the Appliances & rkbook.			Phius			
	Rater/Verifier Confirmed	N/A	PROG REQ.			
nes lighting plan - describe variations, if			Phius			



(September 2025)								
Project								
6 – Renewables & Electrification								
6.0	Site Photos Scan QR Code to view examples of site photos, Don'ts and Do's:							
6.0.1	Site Photos of Renewables & Electrification:	Rater/Veri			N/A			
	Take photos that document the renewables and electrification. Include photos that show context. Site Verification.	Confirmed Save photos into project folder			4. PHIUS+ On-			
6.0.1.1	Solar PV Installed (take photos of inverters and panels).			Т				
6.0.1.2	Electric Vehicle Ready (take photos of electric service panel identifying the branch circuit as "Electric Vehicle Charging").	ne 🔲						
6.0.1.3	Electric Vehicle Supply Equipment (EVSE) (take photos of EV charger or EV charging station(s)).	'						
Notes:		<u> </u>						
6.1 Field Verification  Rater/Verifier is responsible for verifying the tasks below have been completed:								
6.1.1	Renewable Energy Systems:	Rater/\ Confi	/erifier rmed	N/A	PROG REQ.			
6.1.1.1	<b>Solar Thermal System:</b> Installed solar PV system corresponds with shop drawings or purchase order, and document in the Renewables & Electrification tab of the QA Workbook.	[			Phius			
6.1.1.2	Solar Photovoltaic System: Installed solar PV system corresponds with shop drawings or purchase order, and document in the Renewables & Electrification tab of the QA Workbook.							
6.1.2	Electric Vehicle (EV) Charging Infrastructure:	Rater/Verifier Confirmed		N/A	PROG REQ.			
6.1.1.2	Electric Vehicle (EV) Charging Infrastructure: Where parking spaces are provided, installed electric vehicle infrastructure corresponds with shop drawings and achieves the requirements listed in Section 1.3.4.3 of the Phius Guidebook v 24.1.0.				Phius			
6.1.1.3	For non-residential projects and non-residential parts of mixed-use project, document EV Charging Infrastructure in the Renewables & Electrification tab of the QA Workbook.				Phius			
Notes:								
Rater/Verifier Name (Printed):								
Signature:								
Date:								



**DHW** 



**Ducts/Ventilation** 



**Air Leakage** 



**UNIQUE CONDITIONS** 

**WINDOW & DOORS** 

COMPARTMENTALIZATION

**MOCKUPS** 

WHOLE BUILDING

PRELIMINARY TESTS (ONE FLOOR/AREA)

**TRANSITIONS** 

# **TAKEAWAYS**

- Use WUFI Passive as a Guide
- Avoid repetition
- Perform due diligence:
  - Prescriptive vs. Performance Requirements
  - CoRequisite Programs
- Engage the Phius Verifier early

# Thank You

