




What if? A Case for a Multifamily Prescriptive Path

utile

PCA

Who We Are



Jeff Geisinger
AIA, CPHC®
Director of Sustainable
Design
Utile



Darius Luo
CPHC®, EIT, LEED Green
Associate
Building Performance
Specialist
Utile



DiAnn Tufts
LFA, CPHC®, LEED AP BD+C
Director of Sustainable
Design
PCA


Agenda

Introduction

Survey of industry professionals and Phius staff

Project analysis

Where we go from here

The background of the slide is a repeating pattern of isometric line drawings of various building footprints. These include rectangular blocks, L-shaped structures, and smaller individual units, all rendered in a light gray line-art style. The buildings are scattered across the entire page, creating a textured, architectural backdrop.

Introduction

Initial Curiosity

The Motivations:

- Demand for an **easier entry point** to Phius
- Need for **time savings** in the design and review process for already established practitioners
- **Observed patterning** in our portfolios of work


Initial Questions:

- Is there a case to be made for a multifamily prescriptive path?
- Are there trends across our multifamily passive buildings that could inform a streamlined prescriptive standard?


Scope and Process

What this study is:	What this study is not:
<ul style="list-style-type: none">● A survey of practitioners and Phius staff to understand interest in and concerns around a multifamily prescriptive path● An observational analysis of common traits across multifamily passive projects● A set of initial recommendations based on the above for future compliance path updates	<ul style="list-style-type: none">● A draft prescriptive path● A lobbying effort to pressure Phius into creating a prescriptive path● A denunciation of energy modeling

Phius Project Certification Timeline



Energy Modeling



Phius Design Review

2973_R3_DESIGNCERT_2024.03.20.xlsx - Protected View: Saved to this PC >

FileHomeInsertDrawPage LayoutFormulasDataReviewViewAutomateHelpBLUEBEAMAcrobat

K19

X

✓

fx

Case 1: Residential Phius 2024: To Be Reviewed

	A	B	C	D	E	F	G	H	
1	Phius Design Feedback - V5.6					Date:	12/12/2025	02/06/2026	2/20/2026
2	WUFI® Passive Checklist					Certifier Comments		Office Response	Certifier Comments
3	<div>ProjectData</div>	<div></div>	Building	Submitter Name:	Jeff Geisinger			Jeff Geisinger	
4				CPHC Name:	Please confirm				
5				CPHC Phius ID:	*		Confirmed.		
6				Secondary CPHC Name:	If none, please reply "n/a"		104427	Emily Fang	
7				Secondary CPHC Phius ID:	*		119286	119286	
8				Verifier Name:	Please confirm & provide a letter of intent for this project.		See V6. LOI from Rater or Verifier folder.		Hayden Cantoni per PA
9				Verifier Phius ID:	*				LOI_260206'
10				General:	Please confirm project address		See below:		OK, confirmed
11				Project Address:			1R Gurney Street		1R Gurney Street
12				City:	Boston		Boston		Boston
13	State:	Massachusetts		Massachusetts		Massachusetts			
14	Zip Code:	02120		02120		02120			
15	<div>Case</div>	<div>General</div>	<div>Calculation</div>	Certificate Criteria:	Ok, PHius CORE 2024.		Ok, PHius CORE 2024.		
16				Additional notes from Reviewer:	Excellent and very well documented submission. Please review all comments below and reach out via email with any questions!		Please review comments below yellow below, only a few and revisions.		
17				Use WUFI month mean shading factors:	Ok, checked		Ok, checked		
18				Case Reviewed:	Case 1: Residential Phius 2024: To Be Reviewed		Case 1: Residential Phius Reviewed		
19				Version of WUFI Reviewed In:	V3.5.0.1		V3.5.0.1		
20	<div>Report: data & results</div>	<div>Current WUFI Results</div>	<div>General</div>	Heating Demand:	3.97	4.41	4.1		
21				Cooling Demand:	2.46	2.67	3.1		
22				Heating Load:	3.46	3.66	3.1		
23				Cooling Load:	2.52	2.74	2.4		
24				Source Energy:	4.261	4.257	4.2		
25	Site Energy:	20.18	20.36	20.36	20.36				
26	Selection:	Ok, set to 'User Defined'.				Ok, set to 'User Defined'.			
27	Name:	BOSTON LOGAN INT ARPT MA				BOSTON LOGAN INT ARPT MA			
28	Type:	Ok, set to User defined				Ok, set to User defined			

<>

Feedback - MultifamilyGeometryThermal BridgesDHW Pipe LengthsUEF to EFIMEF to MEFI --- +:◀▶🔍

Single Family Prescriptive Path

Prescriptive Requirements

Dimensional

- Compactness (envelope area to floor area ratio) and bedroom density limits

Thermal Envelope

- Envelope: component limits or UA calculation
- No thermal bridging / R-10 everywhere
- Blower door test limit of 0.04 CFM/sf of enclosure

Mechanical Systems

- Ventilation efficiency minimums
- Heating/cooling COP minimums
- No fossil fuel combustion
- Domestic Hot Water: ENERGY STAR UEF or EF
- Laundry and appliances based on ENERGY STAR
- Lighting: ENERGY STAR top quartile

Phius CORE Prescriptive 2021 Snapshot



Input or select data in teal cells

State

MASSACHUSETTS

City

BOSTON LOGAN INT ARP

ASHRAE (169-2021) Climate Zone

5A

iCFA* (ft²)

1500

Number of Bedrooms*

4

Number of Stories

2

*per dwelling unit

1 General

1.1.2

iCFA divided by Number of Bedrooms
(Calculated Value based on Inputs)

Maximum Limit

900

ft²

OK, Meets Limit

375

ft²

3 Compactness

3.1.1

Envelope Area
(Maximum Envelope to Floor Area Ratio)

Maximum

4989

ft²

3.33

4 Solar Protection

4.1.1

Whole Window SHGC

Maximum

NR

4.4.1

Projection Factor for Fixed Overhangs

Minimum

NR

5 Thermal Enclosure

5.1.1a

Fenestration / Openings

Maximum Whole U-Value

0.18

(BTU/h.ft².°F)

5.1.1b

Walls & Overhang Floors - Effective R-value

Minimum Effective R-Value

40

(ft².°F.h/BTU)

5.1.1c

Roofs / Ceilings

Minimum Effective R-Value

71

(ft².°F.h/BTU)

5.1.1d

Whole Slab Foundations, Below-Grade Walls, Floors
of Conditioned Basements & Crawl Spaces

Minimum Effective R-Value

20

(ft².°F.h/BTU)

5.1.1e

Ceilings of Unconditioned Basements or Crawl
Spaces & Pier and Beam Floors

Minimum Effective R-Value

25

(ft².°F.h/BTU)

The background of the slide is a repeating pattern of isometric line drawings of various building shapes, including L-shapes, U-shapes, and rectangular blocks, arranged in a staggered grid.

Survey


Overview and Goals

Reviewers

Single Family Professionals

MA Multifamily Professionals


Who We Surveyed




Survey	Phius Review Staff	Professionals with Prescriptive Path Experience (Single Family)	CPHCs in Massachusetts (Multifamily)
Goals	<ul style="list-style-type: none">Understand experience with prescriptive path reviewIdentify time-consuming aspects of MF project review	<ul style="list-style-type: none">Hear pros/cons of existing prescriptive path	<ul style="list-style-type: none">Identify pros/cons of performance path processGauge interest in potential MF prescriptive path
Assumptions	Reviewers + practitioners (SF) would find prescriptive faster/easier		Multifamily CPHCs would have varied interest in a MF prescriptive path
Respondents	10 reviewers	8 out of 30 (Two non-CPHCs)	36 out of 70

Reviewer Survey

Rounds of review for design certification



Review tasks according to amount of time spent (Multifamily projects)



Reviewer Survey - Things We Heard

Inherent to any multifamily certification path

“
*The review time for all of these [performance path] items is **highly variable and dependent** on CPHC organization and experience level.*

”

“
*Enclosure, component, and system review take the longest because **larger projects** have more details, components, and systems to review.*

”

Note: Any emphasis in the respondents' quotes were added by presenters

Reviewer Survey - Things We Heard

Inherent to any multifamily certification path

“
*The review time for all of these [performance path] items is **highly variable and dependent** on CPHC organization & experience level.*
”

“
*Enclosure, component, and system review take the longest because **larger projects** have more details, components, and systems to review.*
”

Thermal bridge models submitted by CPHCs


“
*Thermal bridge review is a **complete crapshoot** most of the time. It often takes nearly as long to review a thermal bridge calculation as it would to run the analysis myself.*
”

“
*Some teams provide 20+ TB calculations which takes an **abundance of time to review...***
”

Note: Any emphasis in the respondents' quotes were added by presenters

Single Family Survey

Reasons professionals recommend **Phius Prescriptive** over Phius Performance




“
The Prescriptive method simplifies the certification process... and **makes entry into doing a PH certified project easier** for those on the fence.”

“
Since we were new and there is **only one certified consultant in our state**, prescriptive seemed like the best choice.”

Single Family Survey

Reasons professionals recommend **Phius Performance** over Phius Prescriptive




“
Prescriptive path is good for basic shapes and simple buildings. **Anything else should go for performance.**”

“
...At ~4,000 ft2 of wall area that's \$3,720 savings in just 1" of insulation.... You **stack a few simple equations** like that and it's very easy to justify performance path.”

Massachusetts Multifamily CPHC Survey


Valuable aspects of Performance Path



“ Owners want to meet the requirements at the **lowest cost** and **modeling and expertise are invaluable** in achieving that goal. ”

Massachusetts Multifamily CPHC Survey

Time-consuming aspects of Performance Path



“

*Only real annoyance is being asked to analyze conditions or provide additional detail on a model where it **clearly isn't going to move the needle** and the model is comfortably below the targets.*

”


“

*The **level of scrutiny** on minute details these days is proving to be **exhausting** for both us, the design team and the construction team.*

”

Massachusetts Multifamily CPHC Survey

Interest in a multifamily prescriptive path




“

*I do think that **small** [multifamily] buildings... could **greatly benefit** from a prescriptive pathway as long as it is not overly prescriptive and conservative.*

”

Massachusetts Multifamily CPHC Survey

Concerns over a multifamily prescriptive path



“

*The risk with any Prescriptive approach is they tend to be **more conservative** than a modeled pathway...*

”

“

*I really don't want to see our **creativity and freedom constrained**.*

”

Massachusetts Multifamily CPHC Survey

Suggestions we heard

“

*Regardless of whether a prescriptive path is introduced, I believe there should be **changes made to the performance process** to reduce uncertainty, time, and cost.*

”

Massachusetts Multifamily CPHC Survey

Suggestions we heard

“

*Regardless of whether a prescriptive path is introduced, I believe there should be **changes made to the performance process** to reduce uncertainty, time, and cost.*

”

“

*A **prescriptive approach to [thermal bridge] mitigation** would be welcomed as it would reduce modeling time and uncertainty.*

”

“

*I'd like to see an effort to develop a **standardized set of assembly derations** to develop a "worst-case" WUFI model...*

”

“

*A **standard TB library** that can be used for modeling would be great...*

”

Survey - What We Found

Confirmed SF prescriptive path is faster and simpler

- Prescriptive path reduces review rounds
- Prescriptive path provides an easier point of entry due to no modeling requirements and definitive design guidance
- Prescriptive path is more limiting and may not promote design optimization


Confirmed some interest for a MF prescriptive path, esp. smaller buildings

- Concerns over prescriptive path being limiting and disallowing design optimization

Existing performance path could be streamlined

- Many multifamily CPHCs suggested ways to reduce modeling time in current performance path

Thermal bridge submissions can take a disproportionate amount of review time

The background of the slide is a repeating pattern of isometric line drawings of various building footprints. These drawings are in a light gray color and are scattered across the entire slide, creating a textured, architectural background.

Project Analysis

Initial assumptions: Our pattern of regular Phius-compliant strategies could lead to prescriptive guidelines


Project selection

Methodology

Analysis

- Envelope
- Thermal bridging
- MEP systems


Project Selection



Type V
Low Rise (3 to 4 stories)



Type V over I
All Type III




Type III over I
Podium Mid Rise (5 to 7 stories)
Type I (Tower)
High Rise


Number of Projects	25
Architect (Utile / PCA)	60% / 40%
Weather station (Boston Logan / Other MA)	68% / 32%
Cert. status (Design Certified / Certified)	68% / 32%
Market sector (Affordable / Market Rate / Mixed Income)	72% / 12% / 16%
Phius standard (2018, 2021, 2024)	16% / 48% / 36%
% of projects within 5% buffer of Space Conditioning metric (any)	24%
% of projects within 5% buffer of Source Energy metric (excl. solar)	36%

How We Collected Data

WUFI Passive and THERM models, calculators



Construction drawings and architectural knowledge of projects



+ MA multifamily CPHC survey responses on envelope

Above Grade Walls (Wood Construction)

100% 2x6 Studs

Insulation type

% of projects


Continuous Insulation*

Mineral wool	72%
Polyiso board	16%
Insulated sheathing	12%

*Depths varied from 2” to 3”


Cavity Insulation

Blown fibrous insulation (cellulose or fiberglass)	72%
Batt insulation (mineral wool or fiberglass)	24%
Empty	4%




Above Grade Walls - Effective R-values

Wood Framed Walls Only



Overall Wall

Area-weighted across all wall construction types



Note: The single high rise has been excluded for clarity, unless otherwise noted

Windows

Punched Windows

% of projects

uPVC, triple-glazed (median U-0.16)	96%
Fiberglass, triple-glazed	4%





Storefront*

Aluminum, double-glazed (median U-0.39)	68%
Aluminum, triple-glazed (curtain wall)	4%
Fiberglass, triple-glazed	4%

*Storefront only represented an average of 2% of the overall glazing on our projects

Solar Heat Gain Coefficient (SHGC)


SHGC (median at center-of-glass: 0.39)	–
--	---




Windows

Punched Window U-value Ranges

Area-weighted across operable and fixed



Window-to-Wall Ratio (WWR) Ranges



“Punched window U values seem **fairly standardized across all projects**”

— Multifamily survey respondent

Note: Any outliers for survey responses have been removed for clarity, unless otherwise noted

Horizontal Assemblies

Roofs

% of projects

Polyiso above deck (5" to 11")*	100%
Hybrid rigid above, batt or spray below	20%




*Median fastener deration was 13.9% (mild steel) for v2021 and newer projects, vs. 35% default deration

Slabs




Rigid insulation under slab on grade (2" to 5")	88%
Foam glass aggregate under slab	12%

Floors over garage

CCSPF against deck w/ cellulose spray	56%
EPS concrete sandwich	28%
Mineral wool under trusses	8%




Horizontal Assemblies - Effective R-values




Compactness Ratio


Enclosure Area / Interior Conditioned Floor Area (iCFA)



Enclosure / iCFA = **1.26**



Enclosure / iCFA = **1.00**



Enclosure / iCFA = **0.69**

Smaller projects
More surface area to floor area




Larger projects
Less surface area to floor area

Area-Weighted U-Values (Pre-Thermal Bridging)


Vertical U-value v. Compactness

Walls and glazing



Smaller projects → Larger projects

Whole Building U-value v. Compactness



Smaller projects → Larger projects

Thermal Bridges

Perimeter	% of projects
-----------	---------------




Foundation at slab edge	88%
Door sill	16%

Ambient




Steel beam at soffit	36%
Steel at exterior wall	28%
Steel column to beam	28%
Steel beam at garage	28%
Concrete deck to podium	12%
Balcony connection	8%

Interior Footing

Steel column at interior footing	40%
Bearing wall at interior wall footing	20%




Thermal Bridges - Foundation Wall at Slab Edge




Rigid insulation position	Outside (48%)		Combined (33%)		Inside (19%)	
Wall framing above	Wood (3)	Metal (7)	Wood (3)	Metal (3)	Wood (2)	Metal (2)
Psi-value range (Btu/hr-ft-F)	0.016 - 0.02	0 - 0.07	0.02 - 0.04	0.03 - 0.18	0.03 - 0.05	0.06 - 0.65
Psi-value median	0.02	0.03	0.03	0.12	0.04	0.36

Thermal Bridges - Foundation

Weighted Average Perimeter Psi-values



% of Annual Transmission Losses from Foundation TB's




Thermal Bridges

Impact of Thermal Bridges on All Projects




Effect of Garage on Thermal Bridging



Note: Results include data from the single high rise


Mechanical Equipment

ERV Configuration	% of projects
Outside, Centralized	92%
Inside, Individual	8%
Heating/Cooling	
ASHP, VRF	60%
ASHP, 1:1 Split	36%
Condenser loop w/ WSHP	4%
Water Heating	
Central HPWH	48%
Central Gas	36%
Individual Elec. Resistance	12%
Individual HPWH	4%




Energy Recovery Ventilation

Sensible Recovery Efficiency




Electric Efficiency (W/cfm)



Water Heating

Source Energy Buffers (Before Renewables) by DHW System



“ *Electric resistance DHW usually needs PV.* ”
— Multifamily survey respondent

Note: Results include data from the single high rise

Project Analysis - What We Found

Project scale matters


- Low rise projects had commonalities for walls, window-to-wall ratio, and foundation psi values
- Enclosure U-factors trend with project scale (even though horizontal assembly performance varied)
- All projects shared consistency in some things, e.g. glazing and ventilation performance

Some thermal bridges matter more than others

- Foundation TB's contribute relatively little to overall enclosure transmission losses
- Projects w/ garages had more varied thermal bridging and impact on overall performance

Water heating system often determines Source Energy buffer

- Gas or ER DHW closer to Source Energy limits



Where We Go from Here

What We Learned

	Initial assumptions	What we learned
Survey	Practitioners (SF) + reviewers would find prescriptive faster/easier	Confirmed assumptions about time savings Universal concern over prescriptive being too limiting
	Multifamily CPHCs interest in prescriptive	Many multifamily CPHCs suggested ways to streamline the current performance path
Project Analysis	Our pattern of regular Phius-compliant strategies could lead to prescriptive guidelines	Project scale matters Some things we have to model have much more impact than others

What We Learned

Prescriptive

- Early design guidance
- Low barrier to entry
- Shorter certification timeline

Performance

- Decision-making freedom
- More in-depth CPHC involvement
- Customization and trade-offs



Two Opportunities

Prescriptive

Early design guidance
Low barrier to entry
Shorter certification timeline

Performance

Decision-making freedom
More in-depth CPHC involvement
Customization and trade-offs

Middle Ground



Incremental Expansion of the Prescriptive Option


- Start with smaller buildings, where there is need for easier entry to Phius
- Avoid overly conservative limits, incorporate sliding scale

Streamlining the Multifamily Performance Path


- Targeted simplifications of existing modeling and review process
- Standardized details based on expanded project research

Future Multifamily Prescriptive Option

Smaller multifamily / missing middle housing



Streamlining the Multifamily Performance Path



Initial Recommendations

Component	Recommendation	Incremental Expansion of the Prescriptive Path	Streamlining the Performance Path
Enclosure	Consider smaller multifamily eligibility for prescriptive	☐	
	Put enclosure performance limits on a sliding scale (e.g. compactness) and maintain UA trade-off	☐	
	Conduct further study of certified projects in comparable climates to avoid overly conservative limits	☐	
Thermal bridges	Expand detail library to include pre-approved foundation thermal bridges, assembly derations	☐	☐
	Projects with garages may need potential scope limitation, further study		
Mechanical systems	Electric Resistance DHW may need potential scope limitation or PV tradeoff, along with further study		
	Calibrate ventilation and other system performance limits based on further project study	☐	

The background of the slide is a light gray illustration of a city. It features numerous isometric buildings of various shapes and sizes, some with multiple stories and many windows. A large, detailed blimp with a striped pattern and a propeller is positioned in the center-left of the slide, floating above the city. The overall style is clean and modern.

Thank You!

Jeff Geisinger
geisinger@utiledesign.com

Darius Luo
luo@utiledesign.com

DiAnn Tufts
dtufts@pcadesign.com